



# D06.2: AeroMACS Verification Report

## Document information

Project Title	Airport Surface Datalink
Project Number	15.02.07
Project Manager	Indra
Deliverable Name	AeroMACS Verification Report
Deliverable ID	D06.2
Edition	00.01.00
Template Version	03.00.00

## Task contributors

*THALES; SELEX; INDRA; AIRBUS; EUROCONTROL; DSNA*

## **Abstract**

The general purpose of the 15.2.7 project is to verify the AeroMACS Data Link. This document describes the Verification report within the 15.2.7 Project regarding phase 1 testing.

## Authoring – D06-Part 2

Prepared By - <i>Authors of the document.</i>		
Name & Company	Position & Title	Date
██████████ THALES	██████████	30/07/2013
██████████ SELEX ES	██████████	15/11/2013

## Document History

Edition	Date	Status	Author	Justification
00.00.01	05/06/2013	Draft	THALES	New Document
00.00.02	25/06/2013	Draft	SELEX ES	New document reviewed
00.00.03	08/07/2013	Draft	THALES	Thales Test results added
00.00.04	15/11/2013	Draft	SELEX ES	Selex ES Test results added
00.00.05	26/11/2013	Draft	SELEX ES	Fixes and editorial changes and after Thales comments
00.00.06	06/12/2013	Draft	THALES	Reviewer comments taken into account.
00.01.00	06/12/2013	Final	INDRA	Final version for handover to SJU

## Intellectual Property Rights (foreground)

This deliverable consists of SJU foreground.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

# Table of Contents

<b>EXECUTIVE SUMMARY</b> .....	<b>6</b>
<b>1 INTRODUCTION</b> .....	<b>7</b>
1.1 PURPOSE OF THE DOCUMENT.....	7
1.2 INTENDED READERSHIP.....	7
1.3 STRUCTURE OF THE DOCUMENT.....	7
1.4 GLOSSARY OF TERMS.....	8
1.5 ACRONYMS AND TERMINOLOGY.....	8
<b>2 CONTEXT OF THE VERIFICATION</b> .....	<b>10</b>
2.1 SYSTEM OVERVIEW.....	10
2.2 SUMMARY OF VERIFICATION EXERCISE/S.....	12
2.2.1 <i>Summary of Verification Objectives and Success Criteria</i> .....	12
2.2.2 <i>Verification Exercises List and Dependencies</i> .....	13
<b>3 CONDUCT OF VERIFICATION EXERCISES</b> .....	<b>14</b>
3.1 VERIFICATION EXERCISES PREPARATION.....	14
3.2 VERIFICATION EXERCISES EXECUTION.....	15
3.3 DEVIATIONS FROM THE PLANNED ACTIVITIES.....	15
3.3.1 <i>Deviations with Respect to the Verification Strategy</i> .....	15
3.3.2 <i>Deviations with Respect to the Verification Plan</i> .....	15
<b>4 VERIFICATION EXERCISES RESULTS</b> .....	<b>16</b>
4.1 SUMMARY OF VERIFICATION EXERCISES RESULTS.....	16
4.2 ANALYSIS OF VERIFICATION EXERCISES RESULTS.....	17
<b>5 CONCLUSIONS AND RECOMMENDATIONS</b> .....	<b>18</b>
<b>6 REFERENCES</b> .....	<b>19</b>
6.1 REFERENCE DOCUMENTS.....	19
<b>APPENDIX A DETAILED VERIFICATION EXERCISES REPORT</b> .....	<b>20</b>
A.1 VERIFICATION EXERCISE # TLAB_010 REPORT.....	20
A.1.1 <i>Verification Exercise Scope</i> .....	20
A.1.2 <i>Conduct of Verification Exercise</i> .....	20
A.1.3 <i>Verification exercise Results</i> .....	24
A.1.4 <i>Conclusions and recommendations</i> .....	32
A.2 VERIFICATION EXERCISE # TLAB_020 REPORT.....	33
A.2.1 <i>Verification Exercise Scope</i> .....	33
A.2.2 <i>Conduct of Verification Exercise</i> .....	33
A.2.3 <i>Verification exercise Results</i> .....	35
A.2.4 <i>Conclusions and recommendations</i> .....	43
A.3 VERIFICATION EXERCISE # TLAB_030 REPORT.....	44
A.3.1 <i>Verification Exercise Scope</i> .....	44
A.3.2 <i>Conduct of Verification Exercise</i> .....	44
A.3.3 <i>Verification exercise Results</i> .....	45
A.3.4 <i>Conclusions and recommendations</i> .....	46
A.4 VERIFICATION EXERCISE # TLAB_040 REPORT.....	47

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

3 of 100

A.4.1	Verification Exercise Scope.....	47
A.4.2	Conduct of Verification Exercise.....	47
A.4.3	Verification exercise Results .....	49
A.4.4	Conclusions and recommendations .....	56
A.5	VERIFICATION EXERCISE # TLAB_050 REPORT .....	57
A.5.1	Verification Exercise Scope.....	57
A.5.2	Conduct of Verification Exercise.....	57
A.5.3	Verification exercise Results .....	59
A.5.4	Conclusions and recommendations .....	63
A.6	VERIFICATION EXERCISE # LAB1_1 CONNECTION ESTABLISHMENT REPORT .....	64
A.6.1	Verification Exercise Scope.....	64
A.6.2	Conduct of Verification Exercise.....	64
A.6.3	Verification exercise Results .....	67
A.6.4	Conclusions and recommendations .....	76
A.7	VERIFICATION EXERCISE # LAB1_2 POWER CONTROL REPORT .....	76
A.7.1	Verification Exercise Scope.....	76
A.7.2	Conduct of Verification Exercise.....	76
A.7.3	Verification exercise Results .....	77
A.7.4	Conclusions and recommendations .....	80
A.8	VERIFICATION EXERCISE # LAB1_3 QUALITY OF SERVICE REPORT .....	80
A.8.1	Verification Exercise Scope.....	80
A.8.2	Conduct of Verification Exercise.....	80
A.8.3	Verification exercise Results .....	83
A.8.4	Conclusions and recommendations .....	89
A.9	VERIFICATION EXERCISE # LAB1_4 SECURITY REPORT .....	89
A.9.1	Verification Exercise Scope.....	89
A.9.2	Conduct of Verification Exercise.....	89
A.9.3	Verification exercise Results .....	89
A.9.4	Conclusions and recommendations .....	93
A.10	VERIFICATION EXERCISE # LAB1_5 RADIO CHARACTERISTICS REQUIREMENTS REPORT .....	93
A.10.1	Verification Exercise Scope .....	93
A.10.2	Conduct of Verification Exercise.....	93
A.10.3	Verification exercise Results.....	94
A.10.4	Conclusions and recommendations.....	96
A.11	VERIFICATION EXERCISE # LAB1_6 TRANSMIT POWER REPORT .....	96
A.11.1	Verification Exercise Scope .....	96
A.11.2	Conduct of Verification Exercise.....	96
A.11.3	Verification exercise Results.....	97
A.11.4	Conclusions and recommendations.....	99

## List of tables

Table 1: Testing organization.....	10
Table 2: Covered verification Objectives in Phase 1 .....	13
Table 3: Phase 1 Thales lab. Tests .....	13
Table 4: Phase 1 Selex lab. tests .....	13
Table 5: Summary of Thales lab. tests results for phase 1 .....	16
Table 6: Summary of Selex Lab. tests results for phase 1 .....	16

## List of figures

Figure 1: Lab_test_bed_01 (Thales).....	14
Figure 2: Lab_test_bed_02 (Selex).....	15
Figure 3: Picture of test bed in Thales Lab .....	22
Figure 4: AeroMACS Setup on Agilent Spectrum Analyzer .....	64
Figure 5: Picture of test bed in Selex ES Lab .....	65
Figure 6: Spectrum Analyzer connected to AeroMACS BS.....	70
Figure 7: Preamble Detection by MS .....	70
Figure 8: DCD Decoding by MS.....	71
Figure 9: Initial Ranging - the MS receives a RNG_RSP with Status Success .....	71
Figure 10: SS Basic Capabilities Exchange between MS and BS.....	72
Figure 11: Registration procedure and Service Flow Creation .....	73
Figure 12: Initial Network Entry Time.....	75
Figure 13: Open Loop passive Power Control Protocol.....	79
Figure 14: Closed Loop Power Control adjustment at the MS.....	80
Figure 15: QoS - Test bed.....	80
Figure 16: Wireshark Log on ASN-GW ports: no transmission for IP flow not compatible with the SF Classification for DL .....	84
Figure 17: Successful IP Flow in UL .....	85
Figure 18: IPERF Log at the ASN-GW: 2 Mbps requested to be sent in DL .....	86
Figure 19: IPERF Log at the MS: 1Mbps Max Baud Rate respected .....	86
Figure 20: SF1 loaded with 2 Mbps .....	87
Figure 21: SF2 loaded with 3 Mbps .....	87
Figure 22: Baud rate on SF1 .....	88
Figure 23: Baud rate on SF2.....	88
Figure 24: Net Entry without authentication - WS Log.....	91
Figure 25: EAP-based Authentication Procedure .....	92
Figure 26: AeroMACS BS measured Spectral Mask .....	95
Figure 27: Selex AeroMACS BS prototype target spectrum mask .....	95
Figure 28: BS Output Band Power.....	99

## Executive summary

The goal of project 15.2.7, in strong collaboration with Project 9.16, is to define, validate and demonstrate the technical standard based upon existing IEEE 802.16e of the future airport surface data link as foreseen by the aviation community and ICAO. Therefore, it includes the modification of the IEEE 802.16e standard and the developing of a new AeroMACS profile dedicated for airport surface datalink for ATC / AOC services, in order to be compliant with SESAR / ICAO FCI recommendations.

The mentioned evaluation will assess the performance and capacity of the technology by means of analytical work and simulations in order to develop design specifications. Moreover, prototypes were defined and developed to demonstrate results through measurements and trials, in strong coordination with the appropriate standardization bodies.

Therefore, 9.16 and 15.2.7 projects are contributing to the development of an aviation technical standard to be recognized by ICAO in direct and strong cooperation with Eurocae WG82 and RTCA SC 223.

The purpose of the present document is to report tests results corresponding to the verifications performed in project 15.2.7 phase 1 as described in the dedicated 15.2.7. Verification plan [3].

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

6 of 100

# 1 Introduction

## 1.1 Purpose of the document

The overall 15.2.7 verification activity has been divided in two separate working activities phases as described in the verification strategy (see D05.2 document [1]):

- Phase 1 is related to Laboratory Tests only. This Task verifies the main part of the MS/BS Interoperability and RF performances objectives.
- Phase 2 is related both to additional Laboratory Tests and Toulouse Airport Tests (task T10).

Within the 15.2.7 project, verification tests consist in:

- Laboratory tests, held in SELEX and THALES premises, with both partners pieces of equipment,
- Field tests, held in Toulouse Airport, by THALES & DSNA, with THALES pieces of equipment.

The overall verification tests will cover the following aspects:

- MS/BS Interoperability, including AeroMACS Profile,
- RF specification and performances,
- RF performances in real environment (Airport).

This document provides the Verification report for the phase 1 testing activities of the AeroMACS Data Link performed within the 15.2.7 project. It describes the results of the verification exercises defined in the "AeroMACS - verification plan [3]" and how they have been conducted.

## 1.2 Intended readership

This document is a deliverable for the task "WA6: Integration & testing". It is intended to be used primarily by the partners of the 15.2.7 Project. However, for coordination reasons, also Projects SESAR 9.16, SANDRA SP6 and SANDRA SP7 should take this deliverable into account.

Other operational/system projects, like WP3, could make use of the deliverables of 15.2.7/9.16 projects.

## 1.3 Structure of the document

The structure of the document is based on 7 chapters:

- Chapter 1 is an introduction describing the purpose of the document and the intended readership.
- Chapter 2 describes the context of the Verification.
- Chapter 3 gives a brief description of the conduct of the verification exercises.
- Chapter 4 summarizes verification exercises results
- Chapter 5 gives conclusion and recommendations
- Chapter 6 reports in details the results for each test case
- Chapter 7 lists the reference documents

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

7 of 100

## 1.4 Glossary of terms

For terminology clarification, the following terms are defined below:

- “Mock-up” : Part of MS test equipment
- “Prototype” : Base/Mobile station prototype equipment
- “System (test) platform”: Bring together several prototypes, mock-up and tools

## 1.5 Acronyms and Terminology

Term	Definition
<b>ADD</b>	Architecture Definition Document
<b>ATM</b>	Air Traffic Management
<b>CLI</b>	Command Line Interface
<b>DOD</b>	Detailed Operational Description
<b>E-ATMS</b>	European Air Traffic Management System
<b>E-OCVM</b>	European Operational Concept Validation Methodology
<b>GS</b>	Ground Station (Base Station in WiMAX terminology)
<b>IRS</b>	Interface Requirements Specification
<b>INTEROP</b>	Interoperability Requirements
<b>MS</b>	Mobile Station (Subscriber Station or CPE in WiMAX terminology)
<b>OFA</b>	Operational Focus Areas
<b>OSD</b>	Operational Service and Environment Definition
<b>SESAR</b>	Single European Sky ATM Research Programme
<b>SESAR Programme</b>	The programme which defines the Research and Development activities and Projects for the SJU.
<b>SJU</b>	SESAR Joint Undertaking (Agency of the European Commission)
<b>SJU Work Programme</b>	The programme which addresses all activities of the SESAR Joint

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

8 of 100

Term	Definition
	Undertaking Agency.
<b>SPR</b>	Safety and Performance Requirements
<b>SUT</b>	System Under Test
<b>TAD</b>	Technical Architecture Description
<b>TS</b>	Technical Specification
<b>VALP</b>	Validation Plan
<b>VALR</b>	Validation Report
<b>VALS</b>	Validation Strategy
<b>VP</b>	Verification Plan
<b>VR</b>	Verification Report
<b>VS</b>	Verification Strategy

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## 2 Context of the Verification

Project 15.2.7 is a technological project dealing with the adaptation of the WiMAX 802.16-2009 standard (in the aeronautical C band) and with the definition of a profile suited to airport surface communications supporting both ATS and AOC data exchanges.

In this context, the verification approach consists in assessing and collecting evidences on the suitability and performances of the proposed technology (AeroMACS) against the on-going standardization of the new generation of airport data link system, performed in close conjunction with RTCA SC223 and Eurocae WG82.

The objective of the verification phase is thus to perform operational evaluation using lab testing and field trials together with analysis and modeling to deliver the appropriate material for decision making and for preparation of pre-operational and implementation decisions.

### 2.1 System Overview

As already stated, AeroMACS Data Link global overall verification is addressed by Project 15.2.7, but also by Projects 9.16, SANDRA SP6 and SANDRA SP7.

*This section provides the general verification background.*

*Identify the scope of the intended verification: It could be mainly IBP/V&V Platform Verification for WP03 or System / Sub-system / Function Verification for Sys L3 X.Y.Z.*

*Describe who the stakeholders are and how they are concerned by the scope of verification.*

*In any case, tell which systems will be verified. If relevant, tell which Operational Package/Sub-Package/Operational Focus Areas are concerned by the verification scope.*

*Prerequisites to the scoped verification as integration activities or preliminary verification activities are stated at §jError! No se encuentra el origen de la referencia..*

This document focusses on the Verification test cases achieved within the 15.2.7 Project, namely:

- Lab tests: performances measurement related to the new AeroMACS profile and interoperability between different vendors pieces of equipment,
- Field tests: tests in real airport environment focused on the ground segment datalink.

The table below gives an overview of main partners involved in lab and field tests within project 15.2.7 and close contributing project 9.16:

	P 15.2.7	P 9.16
<b>Lab. test</b>	THALES, THALES Lab.	SELEX ES Selex Lab.
	SELEX ES, Selex Lab.	
<b>Field test</b>	THALES + DSNA	SELEX ES + Airbus
	Toulouse airport	Toulouse airport
	Focus on ground component of AeroMACS	Focus on airborne component of AeroMACS

**Table 1: Testing organization**

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## 2.2 Summary of Verification Exercise/s

### 2.2.1 Summary of Verification Objectives and Success Criteria

The verification objectives addressed by the phase 1 can be found in the D05.2 document [1]. They are listed in table below.

General VO Id	Title	VO description
AeroMACS_VO_Interop_01	Profile compliance	Verify that the AeroMACS profile parameters selected in the AeroMACS BS and MS are interoperable, and that they are suited to the SESAR usage.
AeroMACS_VO_Interop_02	Link adaptation	Assessment of the different modulation schemes and the throughput hence supported. Verify proper DCD reception and decoding.
AeroMACS_VO_Interop_03	Network Entry	Verify that AeroMACS MS and BS perform all relevant actions at Network Entry that affects the air interface.
AeroMACS_VO_Interop_04	Quality of Service	Verify that the MS-BS interface supports nrtPS, rtPS and BE QoS classes and the corresponding fields: delay, jitter, packet loss, and throughput.
AeroMACS_VO_Interop_05	SF establishment, change and deletion	Verify the completion of the control messages transmission to successfully complete the creation, change and deletion of a service flow to the MS.
AeroMACS_VO_Interop_07	Dynamic BW allocation	Verification of correct allocation of MAC resources.
AeroMACS_VO_Interop_09	ARQ testing	Verify the correct frame retransmission after packet losses.
AeroMACS_VO_Interop_10	Uplink Power Control	Check that a data transfer continues properly when there is a fading in the UL channel. Verify that MS-BS interface supports the closed loop power control.
AeroMACS_VO_Interop_11	Security functions	Verify that the security functions on the air interface are interoperable between AeroMACS MS and BS. Verify the fragmentation and correct reassembling of the packets and the data integrity (FCS).
AeroMACS_VO_RF_01	Cell Coverage	Verify the cell coverage.
AeroMACS_VO_RF_02	Interferences	Verify the out of band interference level generated.
AeroMACS_VO_RF_03	Spurious emissions	Verify the spurious emissions transmitted by AeroMACS.
AeroMACS_VO_RF_06	Transmission grid	Verify that AeroMACS MS transceiver can be tuned by 250 kHz steps with respect to the 5145 MHz reference frequency.
AeroMACS_VO_RF_07	Power classes	Verify the compliance of AeroMACS BS/MS to one of the defined power classes
AeroMACS_VO_RF_08	Transmit power requirements	Verify AeroMACS Transmit power requirements

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

12 of 100

Table 2: Covered verification Objectives in Phase 1

## 2.2.2 Verification Exercises List and Dependencies

In the first verification phase, SELEX and THALES performed the test cases reported in following tables. The corresponding detailed tests cases as well as their success criteria are to be found in the verification plan for phase 1 (see [3]).

Test Case nr.	Test Case Name	Lab. Environment	VO's addressed
TLAB_010	Profile compliance	Lab_test_bed_01	AeroMACS_VO_Interop_01_A/B/C/D/E
TLAB_020	Quality of Service	Lab_test_bed_01	AeroMACS_VO_Interop_04_A/E AeroMACS_VO_Interop_07_A AeroMACS_VO_Interop_09_A/B/C
TLAB_030	Security	Lab_test_bed_01	AeroMACS_VO_Interop_11_E
TLAB_040	Power & sensitivity	Lab_test_bed_01	AeroMACS_VO_RF_01_B/C AeroMACS_VO_Interop_02_A/B AeroMACS_VO_RF_07_B/C/D/E
TLAB_050	Radio Performances and interferences	Lab_test_bed_01	AeroMACS_VO_RF_06_B/C AeroMACS_VO_RF_02_A AeroMACS_VO_RF_03_A/B AeroMACS_VO_RF_08_F AeroMACS_VO_RF_08_G

Table 3: Phase 1 Thales lab. Tests

Test Case nr.	Test Case Name	Lab. Environment	VO's addressed
LAB1_1	Connection Establishment	LAB1	Interop_01_A/B/C/D/E Interop_03_A/C/D/E/F RFReal_01_A
LAB1_2	Power Control	LAB1	Interop_10_A/B
LAB1_3	Quality of Service	LAB1	Interop_04_B/C/D Interop_05_A Interop_07_A /D
LAB1_4	Security	LAB1	Interop_11_A/B
LAB1_5	Radio Performance	LAB1	RF_06_A/B
LAB1_6	Transmit Power	LAB1	RF_07_A RF_08_A/C/D

Table 4: Phase 1 Selex lab. tests

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

### 3 Conduct of Verification Exercises

#### 3.1 Verification Exercises Preparation

Prior to lab testing, the test beds described in the verification plan ([3]) identified Lab\_test\_bed\_0x (x=1,2) were configured in order to be able to perform the tests in THALES and SELEX labs.

In the verification plan, the Thales test bed was described as follows.




Figure 1: Lab\_test\_bed\_01 (Thales)

Same preparation was performed with Selex test bed as described below.




Figure 2: Lab\_test\_bed\_02 (Selex)

## 3.2 Verification Exercises Execution

Verification Exercises execution took place in the planned time frame for phase 1.

## 3.3 Deviations from the Planned Activities

Most aspects related to the verification activities were described in the Verification Plan. However, even if it was provided in the Verification Plan this may have changed from the planning to the conduction of the verification exercise e.g. modification of a verification objective, requirements not addressed by unexpected constraints during prototype development phase, etc... The purpose of this chapter is to highlight the changes in respect to the content within the Verification Plan.

### 3.3.1 Deviations with Respect to the Verification Strategy

The verification strategy described in the verification plan is applied.

### 3.3.2 Deviations with Respect to the Verification Plan

If any, deviations with respect to the verification plan are highlighted in each verification exercise report in § Appendix A. Slight deviations were noted concerning TLAB\_020, LAB1\_1 and LAB1\_5 Verification Exercises without changing verification strategy (see § A.2.2.3, § A.6.2.3, § A.10.2.3 for detailed description).

## 4 Verification exercises Results

### 4.1 Summary of Verification Exercises Results

The results of the different Verification test cases are summarized in following tables:

- OK: Verification objective achieves the expectations
- NOK: Verification objective does not achieve the expectations

Test Case nr.	Test Case Name	Lab. Environment	VO's addressed	Result
TLAB_010	Profile compliance	Lab_test_bed_01	AeroMACS_VO_Interop_01_A/B/C/D/E	OK
TLAB_020	Quality of Service	Lab_test_bed_01	AeroMACS_VO_Interop_04_A/E AeroMACS_VO_Interop_07_A AeroMACS_VO_Interop_09_A/B/C	OK
TLAB_030	Security	Lab_test_bed_01	AeroMACS_VO_Interop_11_E	OK
TLAB_040	Power & sensitivity	Lab_test_bed_01	AeroMACS_VO_RF_01_B/C AeroMACS_VO_Interop_02_A/B AeroMACS_VO_RF_07_B/C/D/E	OK
TLAB_050	Radio Performances and interferences	Lab_test_bed_01	AeroMACS_VO_RF_06_B/C AeroMACS_VO_RF_02_A AeroMACS_VO_RF_03_A/B AeroMACS_VO_RF_08_F AeroMACS_VO_RF_08_G	OK

Table 5: Summary of Thales lab. tests results for phase 1

Lab Test Case nr.	Test Case Name	Lab. Environment	VO's addressed	Result
LAB1_1	Connection Establishment	LAB1	Interop_01_A/B/C/D/E Interop_03_A/C/D/E/F RFReal_01_A	OK
LAB1_2	Power Control	LAB1	Interop_10_A/B	OK
LAB1_3	Quality of Service	LAB1	Interop_04_B/C/D Interop_05_A Interop_07_A/D	OK
LAB1_4	Security	LAB1	Interop_11_A/B	OK
LAB1_5	Radio Performance	LAB1	RF_06_A/B	OK
LAB1_6	Transmit Power	LAB1	RF_07_A RF_08_A/C/D	OK

Table 6: Summary of Selex Lab. tests results for phase 1

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

## 4.2 Analysis of Verification Exercises Results

The detailed analysis of the verification Exercises can be found in each verification exercise report in §Appendix A.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## 5 Conclusions and recommendations

The main objective of the verification phase is to assess the performances of AeroMACS prototypes.

By analyzing the phase 1 verification results reported in this report, the verification objectives were successfully tested in labs: among others, profile compliance verification, quality of service assessment, sensitivity and radio performances measurement allowed collecting positive evidences on the suitability of the prototypes to assess the AeroMACS technology regarding the on-going standardization.

In conclusion, these phase 1 lab measurements gave a good characterization of the prototypes with positive test results. This gives a good confidence before the field testing to be conducted in Toulouse Airport (phase 2).

This phase 2 testing will gather additional measurements in real environment of Airport surface datalink and thus complement significantly the assessment of the AeroMACS technology in ground segment context with some important information as cell coverage, LOS / nLOS propagation behavior, mobility effect...

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## 6 References

### 6.1 Reference Documents

The following documents were used to provide input:

- [1] P 15.02.07 D05.2 - AeroMACS Verification Strategy
- [2] P 15.02.07 D05.1 - AeroMACS Prototypes Description
- [3] P 15.02.07 D06.1 - AeroMACS Verification Plan

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## Appendix A Detailed Verification Exercises report

This appendix includes the detailed the verification exercise reports.

### A.1 Verification Exercise # TLAB\_010 Report

#### A.1.1 Verification Exercise Scope

Verify that the AeroMACS profile parameters (OFDMA, Channel bandwidth, frame length, TDD, channel frequency) selected in the AeroMACS GS and MS are interoperable.


#### A.1.2 Conduct of Verification Exercise

##### A.1.2.1 Verification Exercise Preparation

*Lab\_test\_bed\_01*

Spectrum Analyzer: Rohde & Schwarz FSV-7 with WiMAX option R&S FSV-K93

The configuration defined for Sesar is loaded before the measurement.



Data Traffic generator/analyzer: IXIA

IXIA is configured with prepared configuration file that generate one traffic stream in each direction (UL and DL).



founding members




Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

Equipment:

MS/GS are configured according to AeroMACS profile. Namely, prepared configuration files are loaded in the equipment:

RF Profile	SESAR_RF_conf2
MCS Profile	SESAR_MCS_conf2
PHY Profile	SESAR_PHY_conf2
MAC Profile	SESAR_MAC_conf2

As an example, main selected physical parameters are: bandwidth 5 MHz, frame length 5 ms, TDD split 32:15, (UL 15 symbols : including 12 symbols for data -pink, 3 reserved for FFB -blue).



Concerning modulation and coding scheme, the whole set of possibilities for DL and for the UL the optional 64 QAM is selected when needed for the test:

<input checked="" type="checkbox"/>	0	QPSK (CTC) 1/2	<input checked="" type="checkbox"/>	1	QPSK (CTC) 1/2
<input checked="" type="checkbox"/>	1	QPSK (CTC) 3/4	<input checked="" type="checkbox"/>	2	QPSK (CTC) 3/4
<input checked="" type="checkbox"/>	2	16-QAM (CTC) 1/2	<input checked="" type="checkbox"/>	3	16-QAM (CTC) 1/2
<input checked="" type="checkbox"/>	3	16-QAM (CTC) 3/4	<input checked="" type="checkbox"/>	4	16-QAM (CTC) 3/4
<input checked="" type="checkbox"/>	4	64-QAM (CTC) 1/2	<input checked="" type="checkbox"/>	5	64-QAM (CTC) 1/2
<input checked="" type="checkbox"/>	5	64-QAM (CTC) 2/3	<input checked="" type="checkbox"/>	6	64-QAM (CTC) 2/3
<input checked="" type="checkbox"/>	6	64-QAM (CTC) 3/4	<input checked="" type="checkbox"/>	7	64-QAM (CTC) 3/4
<input checked="" type="checkbox"/>	7	64-QAM (CTC) 5/6	<input checked="" type="checkbox"/>	8	64-QAM (CTC) 5/6

MS & GS are linked together according to test bed configuration with proper attenuation and switched on.



Figure 3: Picture of test bed in Thales Lab

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

### A.1.2.2 Verification Exercise execution

Step	action	Action result	PCO	Result
1	Set frequency on the GS : - 5120,5 MHz Provision new RF parameter on the GS	New frequency provisioned on GS	GS control MMI Spectrum analyzer	OK
2	Set frequency scan of MS : - 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz.)	MS connects eventually to the GS	GS control MMI	OK
3	Initiate traffic in the UL or DL thanks to the traffic generator (either Ixia or lperf)	Communication established in both directions (UL and DL)	Ixia	OK (Ixia)
4	Confirm the GS OFDMA mode (Spectrum analyzer on GS side)	GS Preamble demodulated	Spectrum Analyzer	OK
5	Measure the GS bandwidth (Spectrum analyzer on GS side) Note: Focus on main channel + adjacent + alternate	Most of Energy included in main central channel 5 MHz	Spectrum Analyzer	OK
6	Measure the GS Frame Length (Spectrum analyzer on GS side)	Frame of 5 ms	Spectrum Analyzer	OK
7	Check that MS and GS operate in TDD mode (Spectrum analyzer on GS side)	MS et BS alternately emits with ratio as defined on the GS  (Note: activity seen only on DL as UL is attenuated by directional coupler to spectrum analyzer)	Spectrum Analyzer	OK
8	Set frequency on the GS : - 5093,5 MHz	MS connect to new GS frequency	GS control MMI	OK
9	Set frequency on the GS : - 5147,5 MHz	MS connect to new GS frequency	GS control MMI	OK
10	Set frequency on the GS : - 5098.5	MS connect to new GS frequency	GS control MMI	OK
11	Set frequency on the GS : - 5103.5	MS connect to new GS frequency	GS control MMI	OK

12	Measure the MS bandwidth (Spectrum analyzer on MS side)	Bandwidth 5 MHz	Spectrum Analyzer	OK
----	--	-----------------	-------------------	----

### A.1.2.3 Deviation from the planned activities

None.

## A.1.3 Verification exercise Results

### A.1.3.1 Summary of Verification exercise Results

- Step 4: OFDMA mode verified
- Step 5/12: GS/MS 5MHz bandwidth confirmed
- Step 6: Frame Length measured and OK
- Step 7: TDD Mode verified
- Step 8/9: Edge frequencies reached
- Step 10/11: Complementary measurement at future airport frequencies OK.

### A.1.3.2 Analysis of Verification Exercise Results

The testing of these core AeroMACS functionalities (OFDMA, TDD, Frame length, frequency) are done through a configured spectrum analyzer with WiMAX measurement functions.


DL synchronization and frame structure verification done at 5120,5 MHz and also at 5093,5 and 5098,5 MHz, 5147,5 MHz is shown below (Spectrum analyzer was wired on BS side so that UL bursts are sufficiently attenuated to focus on DL activity). One can see that the DL OFDM burst is properly synchronized and demodulated.

founding members




Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

24 of 100



Date: 29.MAY.2013 17:00:06




Date: 30.MAY.2013 18:21:44


founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu



Date: 29.MAY.2013 19:05:37




Date: 2.JUL.2013 10:16:03

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

Below is given an example of DL demodulation with 64QAM traffic and 16QAM traffic.




Date: 12.JUL.2013 13:54:12

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu





Date: 24.JUL.2013 11:36:12

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu


Same positive result for the UL OFDM burst (example below at 5103,5 MHz for QPSK, 16QAM, 64QAM) (spectrum analyzer was wired on MS side so that DL bursts are sufficiently attenuated to focus on UL activity).



founding members





Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu




On the pictures above, measured frame duration is 5 ms (3 repetitions can be observed as the analysis time duration of spectrum analyzer is tuned to 15 ms). Detailed time measurements reveals an active DL Burst of 3,2 ms long and an UL burst of 1,5 ms long, consistent with ratio 32:15. The TDD nature of the frame is also clearly shown.

About the 5 MHz bandwidth, it was confirmed through spectrum measurement as shown below, where energy is concentrated on the centered 5 MHz channel for the edges of the band and the center.





Date: 4.JUL.2013 10:05:46



Date: 4.JUL.2013 09:58:22

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

### A.1.3.3 Unexpected Behaviors/Results

None.

### A.1.4 Conclusions and recommendations

The testing allowed checking the core AeroMACS functionalities (OFDMA, TDD, Frame length, frequency). No recommendations for next phase (Airport tests) as all verification objectives are addressed satisfactory.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## A.2 Verification Exercise # TLAB\_020 Report

### A.2.1 Verification Exercise Scope

Test QOS: verify the traffic priority functionality, verify SF BE rules, verify of correct allocation of MAC resources and verify the correct frame retransmission after packet losses in case of ARQ or not.

### A.2.2 Conduct of Verification Exercise

#### A.2.2.1 Verification Exercise Preparation

Same as for TLAB\_010 see § A.1.2.1.

Additionally, QOS service flows are configured as defined in verification exercise execution.

#### A.2.2.2 Verification Exercise execution

Step	action	Action result	PCO	Result
P1: Test QOS priority				
1	Set frequency on the GS : - 5120,5 MHz Switch on the GS	GS on	GS control MMI	OK
2	Configure on the GS two SF, each with a different classifier based on @IP source from each source. The SFs have the same characteristics except the priority: in one case 0 and in the other case 7.	SF defined	GS control MMI	OK
3	Set frequency scan of MS : - 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz) Switch on the MS	MS connects eventually to the GS	GS control MMI	OK
4	Tune the variable attenuator so to obtain the max available modulation.	64QAM	GS control of MMI	OK
5	Simulate two UP streams on the IXIA generator with two different @IP sources. The sum of data rate is more than can be achieved with QPSK and less that can be achieved with 64QAM	Communication established with no packet loss	IXIA MMI GS control MMI	OK
6	Increase the attenuation so to obtain a QPSK modulation. Data rate decreases.	QPSK	GS control of MMI	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

33 of 100

7	Check that the stream with less priority is affected first by data rate downgrade.	Packet loss on the stream with less priority	IXIA	OK
P2: test BE				
1	Configure on the GS one DL SF of BE type with a maximum data rate of 300 kbps and a classifier based on any stream. Check that for BE type only the max data rate can be set.	BE parameters set	GS control MMI	OK
2	Simulate one DL stream on the IXIA generator with a data rate of 1 Mbps.	One stream generated.	IXIA GS control MMI	OK
3	Check that the DL stream data rate is limited corresponding to the max data rate of SF.	Data rate limited to 300 kbps	IXIA GS control MMI	OK
P3: ARQ testing				
1	ARQ is activated on the BS. Simulate a data stream through IXIA and generate some impairments: attenuation at the sensitivity limit of a modulation (modulation is fixed, ACM disabled). Check the packet losses after a long time	Packet losses written down and latencies	IXIA	OK
2	ARQ is deactivated on the BS, modulation is fix, ACM disabled. Simulate a data stream through IXIA and same attenuation as above. Check the packet losses after a long time	Packet losses written down and latencies	IXIA	OK
3	Compare the packet losses and latencies	Packet losses in greater when no ARQ	IXIA	OK
P4: BW allocation				
1	Configure on the GS one UL SF of BE type.	SF parameters set	GS control MMI	OK
2	First generate a stream corresponding to BE service flow and almost max data rate.	Check that stream is generated and that bandwidth is allocated only when stream is generated	IXIA	OK
3	Configure on the GS with one UL SF of UGS type a fixe bandwidth can be allocated.	SF UGS parameters set. Bandwidth allocated to UGS even if no streams generated for this SF. BE stream reduced.	GS control MMI IXIA	OK

### A.2.2.3 Deviation from the planned activities

In P4.3 steps on the test, the test is adapted as follows to be executed based on the guaranteed rate of the flows. BE and UGS streams are generated simultaneously, and one shall observe that, in case of bandwidth shortage, the stream related to UGS is prioritized compared to the BE one and that the UGS stream is maintained in a regular way (for UGS scheduling the BS provides the MS with fixed size grants in a periodic manner) whereas in the BE case the allocated bandwidth to the stream varies (for BE scheduling the BS does not provide dedicated polling opportunities to the MS).

## A.2.3 Verification exercise Results


### A.2.3.1 Summary of Verification exercise Results


- Phase 1: QOS priority is working as expected. The stream classified in a SF with the higher priority is privileged.
- Phase 2: It was verified that the Best Effort type QOS essentially offers to set a max data rate limit and the test shows that it is correctly enforced by the equipment.
- Phase 3: ARQ testing performed better than Non ARQ in terms of packet loss.
- Phase 4: It was correctly observed that the UGS service flow takes over the BE service flow and that the MS, in case of UGS, is provided with fixed size grants regarding bandwidth allocation.

### A.2.3.2 Analysis of Verification Exercise Results

- Phase 1: QOS priority


Two UL SF of BE type are defined. One with the lowest priority for the data coming from IP address 192.168.0.67 and one with the highest priority for the data coming from IP address 192.168.0.57. A data rate shortage is created by increasing the attenuation on the link (downgrading of modulation), and the resulting aggregate data rate is lower than the required data rate for data transmission. The observation is that the data flow with a SF of higher priority is privileged over the one with a lower priority in terms of bandwidth allocation.





- Phase 2: Best Effort



The QoS parameters associated with BE service are maximum sustained traffic rate and traffic priority. It was observed that a data flow with more than the maximum allowed data rate is limited to max. This is showed on following picture. One UL and one DL BE SF with 300 kbps max are defined. When transmitted more than 300 kbps, the received data rate is limited to 300 kbps.



- Phase 3: ARQ testing

The test consists in verifying that an ARQ connection compared to a non ARQ connection in the same radio conditions, has less packet losses and higher latency, due to the fact that packet are retransmitted.

This is shown in the two pictures below where the attenuator is tuned to be at the sensitivity limit: same signal conditions but in the first case ARQ is activated and in the second case it is deactivated. In first case, we are able to observe that the packet losses are maintained low whereas latency increases due to packet retransmission and in the second case, as no packet retransmission occurs, packet losses increase regularly.




founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

Additional tests are presented below with ARQ enabled. The variable attenuator is tuned one dB below sensitivity threshold (so that packet losses begin) and back above sensitivity threshold. One can see the effect of packet retransmissions to reduce packet losses.




founding members




Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

- Phase 4: Bandwidth allocation

Two UL service flows were defined with same priority and same max sustained rate. One is BE and associated with IP SRC 192.168.0.57 and the other is UGS with IP SRC 192.168.0.67. A data rate shortage is then created by increasing the attenuation on the link (downgrading of modulation), and the resulting aggregate data rate is lower than the required data rate regarding the data traffic to transmit. One can see that UGS is privileged over BE.






founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

In following pictures, one can see that bandwidth allocation granted to MS in case of UGS is fix and stable while the allocation for BE is erratic in time.



### A.2.3.3 Unexpected behaviors/Results

None.

### A.2.4 Conclusions and recommendations

The testing allowed checking QOS functionalities.

## A.3 Verification Exercise # TLAB\_030 Report

### A.3.1 Verification Exercise Scope

Security: verify that BS and MS are able to use encryption.

### A.3.2 Conduct of Verification Exercise

#### A.3.2.1 Verification Exercise Preparation

Same as for TLAB\_010 see § A.1.2.1.

Additionally, a AAA server was used (Freeradius.Net 1.1.7-r0.0.2).

#### A.3.2.2 Verification Exercise execution

Step	action	Action result	PCO	Result
1	Set frequency on the GS : - 5120,25 MHz Switch on the GS AAA server is on	GS on	GS control MMI	OK
2	Set frequency scan of MS : - 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz.) Switch on the MS	MS connects eventually to the GS	GS control MMI	OK
3	Ping the MS from the PC of the GS	Ping OK	PC MMI	OK (PC of MS)
4	Sent file via FTP from the PC of the GS to the PC of the MS	File transfer done	PC MMI	OK
5	Deregister MS Remove secret information on MS	MS tries to connect without success to the GS	GS control MMI	OK
6	Deactivate authentication on the GS.	MS connects eventually to the GS	GS control MMI	OK
7	Sent file via FTP from the PC of the GS to the PC of the MS	File transferred (cyphering not used)	PC MMI	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

44 of 100

### A.3.2.3 Deviation from the planned activities

None

## A.3.3 Verification exercise Results


### A.3.3.1 Summary of Verification exercise Results

The test showed that the Authentication, Authorization, and Accounting (AAA) process performed as expected.

### A.3.3.2 Analysis of Verification Exercise Results

We observed that when the MS was well configured with the certificates and other secret information (password...), it was correctly authenticated and authorized to communicate. Without this mandatory information, the MS was not authorized to register.

To illustrate this, below we can see two captures by Wireshark of the Radius exchanges with the AAA server: one shows the Access-Request message from MS relayed to the AAA server and the other shows the Access-Accept response message from the AAA server.



```
1930 287.554209000 192.168.0.1 192.168.0.105 RADIUS 225 Access-Accept(2) (id=107, l=183)
  Frame 1930: 225 bytes on wire (1800 bits), 225 bytes captured (1800 bits) on interface 0
  Ethernet II, Src: Dell_02:02:01:bd (a4:ba:db:02:01:bd), Dst: Afspar_ca:6e:e3 (00:a0:0a:ca:6e:e3)
  Internet Protocol Version 4, Src: 192.168.0.1 (192.168.0.1), Dst: 192.168.0.105 (192.168.0.105)
  User Datagram Protocol, Src Port: radius (1812), Dst Port: radius (1812)
  RADIUS Protocol
    Code: Access-Accept (2)
    Packet identifier: 0x6b (107)
    Length: 183
    Authenticator: 08456e080ab30f1a0f4f128c89e5ebfe
    [This is a response to a request in frame 1929]
    [Time from request: 0.011265000 seconds]
    Attribute value Pairs
      AVP: l=58 t=Vendor-Specific(26) v=Microsoft(311)
      AVP: l=58 t=Vendor-Specific(26) v=Microsoft(311)
      AVP: l=6 t=EAP-Message(79) Last Segment(1)
        EAP Fragment
          Extensible Authentication Protocol
            Code: Success (3)
            Id: 12
            Length: 4
            AVP: l=18 t=Message-Authenticator(80): 7b3e0f74f4bffc624e1fb838c1f81f
            AVP: l=23 t=User-Name(1): FreeeRADIUS.net-Client
  0000 0c 00 04
  Frame (225 bytes) Reassembled EAP (4 bytes)
```

### A.3.3.3 Unexpected behaviors/Results

None.

### A.3.4 Conclusions and recommendations

It was verified that the equipment properly implement authentication via the AAA server to handle an encrypted communication.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

## A.4 Verification Exercise # TLAB\_040 Report

### A.4.1 Verification Exercise Scope

Verify the modulation and coding schemes supported by MS and BS, measure the modulation sensitivity assess the dynamic modulation change and check the MS/BS maximum tolerable input.

### A.4.2 Conduct of Verification Exercise

#### A.4.2.1 Verification Exercise Preparation

Same as for TLAB\_010 see § A.1.2.1.

Verification Exercise execution

Step	action	Action result	PCO	Result
Phase 1 : measure performances of the uplink				
1	On the GS control MMI: <ul style="list-style-type: none"> <li>- Set frequency : 5093,5 MHz</li> <li>- UL sub channelization is set to fix</li> <li>- Fix the UL modulation to 64QAM 5/6</li> </ul> Provision the GS	GS new parameters provisioned	GS control MMI	OK
2	Set frequency scan of MS : <ul style="list-style-type: none"> <li>- 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz.)</li> </ul>	MS connects eventually to the GS	GS control MMI	OK
3	Initiate a communication between MS and GS.	Communication established in UL direction	IXIA	OK
4	Tune the variable attenuator so to obtain the Max Power on the MS and to be at the limit of sensitivity.  Then, write down the RSSI level of the GS and the max attenuation of the link.	Obtained values: Attenuation, GS RSSI, MS emitting power, UL data rate  Deduce the sensitivity of the GS and the max emitting power of the MS	GS MMI, MS MMI	OK
5	Do step 1 to 4 with each available UL modulation: 64 QAM $\frac{3}{4}$ , 16QAM $\frac{3}{4}$ , 16QAM $\frac{1}{2}$ , QPSK $\frac{3}{4}$ , QPSK $\frac{1}{2}$			OK
Phase 2 : measured performances of the downlink				
1	On the GS control MMI:	GS on	GS control MMI	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

47 of 100

	<ul style="list-style-type: none"> <li>- Set frequency : 5103,5 MHz</li> <li>- Fix the DL modulation to 64QAM 5/6</li> <li>- GS power fixed to max</li> </ul> <p>Switch on the GS</p>			
2	<p>Set frequency scan of MS :</p> <ul style="list-style-type: none"> <li>- 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz.)</li> </ul> <p>Switch on the MS</p>	MS connects eventually to the GS	GS control MMI	OK
3	Initiate a communication between the GS and the MS.	Communication established in DL direction	Ixia	OK
4	<p>Tune the variable attenuator so to be at the limit of sensitivity.</p> <p>Then, write down the RSSI level of the GS and the max attenuation of the link.</p>	<p>Obtained values:</p> <p>Attenuation, MS RSSI, GS emitting power, DL data rate</p> <p>Deduce the sensitivity of the MS</p>	GS MMI, MS MMI	OK
5	Do step 1 to 4 with each available UL modulation: 64 QAM $\frac{3}{4}$ , 16QAM $\frac{3}{4}$ , 16QAM $\frac{1}{2}$ , QPSK $\frac{3}{4}$ , QPSK $\frac{1}{2}$			OK
<b>Phase 3 : threshold between automatic modulation / coding changes</b>				
1	<p>On the GS control MMI:</p> <ul style="list-style-type: none"> <li>- Set frequency : 5098,5 MHz</li> <li>- Automatic Modulation</li> <li>- GS power fixed to max</li> </ul> <p>Switch GS on and MS on</p>	GS on. MS connects eventually to the GS	GS control MMI	OK
2	Initiate a communication in both direction.	Communication established in UL and DL direction	Ixia	OK
3	<p>Tune the variable attenuator from less attenuation to more attenuation so to obtain modulation change in the UL and the DL.</p> <p>Write down the attenuation corresponding to each modulation change.</p>	<p>Obtained values:</p> <p>Attenuation versus modulation change</p>	GS control MMI	OK
<b>Phase 4: Max tolerable input signal at MS</b>				
1	On the GS control MMI:	GS on. MS connects	GS control MMI	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

	<ul style="list-style-type: none"> <li>- Set frequency : 5093,5 MHz</li> <li>- DL sub channelization is set to fix</li> <li>- Fix the DL modulation to QPSK <math>\frac{3}{4}</math></li> </ul> <p>Switch on the GS</p>	eventually to the GS		
2	Initiate a communication between the GS and the MS: DL.	Communication established in DL direction	IXIA	OK
3	Tune the variable attenuator to increase receive level at MS.  Write down the attenuation when error occurs.	Receive power threshold of degradation	IXIA	OK

#### A.4.2.2 Deviation from the planned activities

None.

#### A.4.3 Verification exercise Results

##### A.4.3.1 Summary of Verification exercise Results

The results are summarized below:

- Phase 1: measure performances of the uplink
  - o UL measured sensitivity and max data rate are summarized in table below. Measurements are made with BS1 @ 5093,5 MHz.

UL Mod	UL Sensitivity	UL Max datarate
64 qam 2/3	-71 dBm	1,91 MBps
64 qam 1/2	-82 dBm	1,42 MBps
16 qam 3/4	-82 dBm	1,42 MBps
16 qam 1/2	-84 dBm	0,94 MBps
qpsk 3/4	-86 dBm	0,69 MBps
qpsk 1/2	-94 dBm	0,45 MBps

Note: 64QAM is optional in AeroMACS for the uplink.

Note: With sub-channelization (down to 2 sub-channels used out of the 17 sub-channels) a gain of more than 6 dB is observed (of course the effect is reduced data rate).

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

- Phase 2: measured performances of the downlink is summarized in following tables
  - o Measured sensitivity @ 5103,5 MHz with BS2 is summarized in table below

Modulation scheme	DL Sensitivity
64 qam 5/6	-73 dBm
64 qam 3/4	-77 dBm
64 qam 2/3	-79 dBm
64 qam 1/2	-82 dBm
16 qam 3/4	-83 dBm
16 qam 1/2	-87 dBm
qpsk 3/4	-91 dBm
qpsk 1/2	-93 dBm

- o DL Measured data rate is summarized in table below

Mod & coding rate	DL Measured Data rate [Mb/s]
64QAM 5/6	9,2
64QAM 3/4	8,3
64QAM 2/3	7,4
64QAM 1/2	5,5
16QAM 3/4	5,5
16QAM 1/2	3,7
QPSK 3/4	2,7
QPSK 1/2	1,8

- Phase 3 : threshold between automatic modulation / coding changes

- o In the Downlink:

Auto DL Mod switching	Received level
64 qam 5/6 -> 64 qam 3/4	-74 dBm
64 qam 3/4 -> 64 qam 2/3	-77 dBm
64 qam 2/3-> 64QAM 1/2	-79 dBm
64QAM 1/2-> 16 qam 3/4	-83 dBm
16 qam 3/4-> 16 qam 1/2	-84 dBm
16 qam 1/2-> qpsk 3/4	-86 dBm
qpsk 3/4-> qpsk 1/2	-90 dBm

- o In the Uplink:

Auto UL Modulation change	Received level
16 qam 3/4-> 16 qam 1/2	-78 dBm
16 qam 1/2-> qpsk 3/4	-83 dBm
qpsk 3/4-> qpsk 1/2	-85 dBm

- Phase 4: a -30 dBm input signal is OK at MS receiver.

### A.4.3.2 Analysis of Verification Exercise Results

The results are analyzed below:

- DL & UL Data rates are consistent with what was calculated in theory.
- DL & UL Sensitivity is examined relatively to the theoretical table of SRD. The measured sensitivity is between 1 to 2 dB better than theoretical value. Transition margin for automatic modulation / coding changes is found to be consistent with sensitivity measurements.
- In UL, sub-channelization allows greater attenuation hence greater distance (at the prize of a reduced data rate).



Some IXIA Screenshots to illustrate the results the data rates achieved with 64QAM  $\frac{3}{4}$ , 16 QAM  $\frac{3}{4}$ , QPSK  $\frac{3}{4}$  in the downlink.

The screenshot displays the IXIA NetworkMiner interface. The main window shows a table of traffic flow groups. The 'Flow Rate' column for the selected traffic item is circled and labeled as 8.3 Mbps. Below this, the 'Flow Statistics' table provides detailed metrics for each traffic item.

Transmit State	Suspend	Tx Port	IPv4 :Source Address	Rx Ports	Flow Group Name	Configured Frame Size	Applied Frame Size	Frame Rate
1		BS	IPv4 :Source Address- 192.168.0.47	CPE;	Traffic Item 1-EndpointSet-1 - Flow Group 0...	Fixed: 1400	Fixed: 1400	8.3 Mbps
2		CPE	IPv4 :Source Address- 192.168.0.57	BS;	Traffic Item 1-EndpointSet-1 - Flow Group 0...	Fixed: 1400	Fixed: 1400	1 Mbps

Tx Port	Rx Port	Traffic Item	IPv4 :Source Address	Tx Frames	Rx Frames	Frames Delta	Loss %
1	CPE	Traffic Item 1	192.168.0.47	96,323	96,323	0	0.000
2	BS	Traffic Item 1	192.168.0.57	11,606	11,606	0	0.000





Some screenshots for max data rates in the UL are shown below (the data rate is shown at sensitivity limit).

founding members





Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu



founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu




founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

Below the effect of sub channelization in the UL is depicted:




Date: 24.JUL.2013 15:56:25

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu



Date: 24.JUL.2013 15:49:38

### A.4.3.3 Unexpected behaviors/Results

None.

### A.4.4 Conclusions and recommendations

Measurements performed well. With sub channelization, we can expect to see an increase in cell coverage but with less data rate.

For next phase, one recommendation could be (if possible regarding installation of two antennas in the vehicle) to complement the test in Toulouse Airport with MIMO A for the mobile stations (context of ground segment) in order to assess any improvement in reception performances.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

## A.5 Verification Exercise # TLAB\_050 Report

### A.5.1 Verification Exercise Scope

The test purpose is to measure radio performances (power spectral flatness, interferences, unwanted emissions).

### A.5.2 Conduct of Verification Exercise

#### A.5.2.1 Verification Exercise Preparation

Same as for TLAB\_010 see § A.1.2.1.

#### A.5.2.2 Verification Exercise execution

Step	action	Action result	PCO	Result
1	Set frequency on the GS : - 5120,5 MHz Switch on the GS	GS on	GS control MMI	OK
2	Set frequency scan of MS : - 5093,5 – 5147,5 MHz, step 250 kHz (5002,5 + n*0.25 for n = {364...580} in MHz.) Switch on the MS	MS connects eventually to the GS	GS control MMI	OK
3	Initiate a communication in both directions.	Communication established in both directions (UL and DL)	IXIA	OK
<b>Phase 1: Spectrum mask measurement</b>				
1	Measure spectrum Mask and check flatness of the 5 MHz BW of GS	Spectrum measurement of the 5MHz channelization. Measurement of the flatness.	Spectrum Analyzer	OK
2	Measure spectrum Mask and check flatness of the 5 MHz BW of MS	Spectrum measurement of the 5MHz channelization. Measurement of the flatness.	Spectrum Analyzer	OK
3	Tune BS to other frequencies and go to 1 5093,5 MHz – 5098,5 MHz – 5103,5 MHz – 5147,5 MHz	MS connects eventually to the GS		OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

57 of 100

Phase 2: Test the unwanted emission level outside the band				
1	Set frequency on the GS : 5093,5 MHz	Frequency tuned	GS control MMI	OK
2	Measure the spurious emission out of band (particular focus on f= 5126 MHz (AMT) & on f=5038,8 MHz (MLS))	Delta measurement of out band compared to in band signal	Spectrum Analyzer	OK
3	Tune BS to 5103,5 MHz and go to 2	Frequency tuned	GS control MMI	OK

### A.5.2.3 Deviation from the planned activities

None

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)

## A.5.3 Verification exercise Results


### A.5.3.1 Summary of Verification exercise Results

- Phase 1: The 5 MHz spectrum was measured through the spectrum analyzer at the different frequency including the adjacent and alternate channels. It complies with specified mask.
- Phase 2: An analysis is made over the frequencies to detect the unwanted emissions. They are below the specified maximum level.

### A.5.3.2 Analysis of Verification Exercise Results

- Phase 1:

The specified spectrum mask is as follows:




As an example reported for analysis, one can find below the measurement results for the 5093,5 and 5103,5 MHz frequency which are planned to be used at the Toulouse Airport.

5103,5 MHz DL spectrum is represented below. It fits the mask.



Date: 24 JUN 2013 17:35:41

UL spectrum @ 5103,5 MHz represented below fits also the mask.



Date: 30 MAY 2013 12:02:12

As a confirmation of the analysis, another spectrum measurement is presented for the DL & UL 5093.5 MHz frequency: it is also in conformance with mask.


founding members




Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu



Two additional tested frequencies UL 5120,5 MHz and UL 5098,5 MHz are given below.



Besides, below a measurement about flatness is highlighted, showing flatness is also OK.




Date: 12.JUL.2013 13:19:41

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

- Phase 2: Unwanted emissions measurement at output of MS and BS equipment are analyzed below with respect of the frequencies that will be used at the Toulouse airport (5093,5 MHz and 5103,5 MHz). A particular focus is done on the MLS frequency (5038,8 MHz) and the AMT frequency (5126 MHz).



The maximum spurious level is at least 53 dB below the max. If we consider the BS emitting at 23 dBm over 5 MHz, this gives a level of 7 dBm in the RBW100 kHz corresponding to a level of spurious below -46 dBm in RBW 100 kHz.

### A.5.3 Unexpected behaviors/Results

None.

### A.5.4 Conclusions and recommendations

The stations perform well regarding spectrum mask and spurious. No particular recommendation for next phase testing.

## A.6 Verification Exercise # LAB1\_1 Connection Establishment Report

### A.6.1 Verification Exercise Scope

The purpose of this Verification Exercise is checking that the MS properly connects with the BS, and that both the devices under test (MS and BS) are compliant with the specific AeroMACS RF requirements detailed in the Verification Exercise execution Section.

### A.6.2 Conduct of Verification Exercise

#### A.6.2.1 Verification Exercise Preparation

The test bed described in Figure 2 was arranged. The following main components were used:

Spectrum Analyzer: Agilent E4445A PSA Series, 3Hz-13.2GHz; 89600 VSA SW (Build 15.01.356.0).

The specific AeroMACS setup is loaded before test execution.




Figure 4: AeroMACS Setup on Agilent Spectrum Analyzer

#### Equipment:

MS/BS are configured according to AeroMACS profile (BW 5MHz, frame length 5 ms, TDD Mode, DL/UL split (e.g. 32:15), etc.). In particular, prepared configuration files are pre-loaded in the equipment. For instance, in the BS it is possible to set the BS IP address, the IP address of used ASN GW, Base Station ID, and some other internal parameters.

ASN-GW is an Aricent Wing ASN-GW.

MS, BS and ASN-GW were linked together according to test bed configuration with proper attenuation and switched on.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu



**Figure 5: Picture of test bed in Selex ES Lab**

Fading Simulator and Data Traffic Generator shown in Figure 2 were not used in this test.

### A.6.2.2 Verification Exercise execution

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on MS	Set the center frequency modifying the MS config file and reboot	MS CLI	OK
2.	Verify that MS begins scanning for BS	Check MS status	MS CLI, MS indicator LEDs	OK.
3.	Switch on BS			OK
4.	Configure BS to first channel (5093.5 MHz)	Set the center frequency using CLI BS  Reboot BS	BS CLI	OK
5	Reboot BS			OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

6.	Verify that MS connects successfully		MS CLI, MS indicator LEDs	OK
7.	Verify that both BS and MS use orthogonal frequency-division multiple access		WiMAX Vector Spectrum Analyzer	OK
8.	Verify that both BS and MS use 5 MHz Channel Bandwidth		WiMAX Vector Spectrum Analyzer	OK
9.	Verify that both BS and MS use 5 ms frame length		WiMAX Vector Spectrum Analyzer	OK
10.	Verify that both BS and MS are able to operate in TDD mode		WiMAX Vector Spectrum Analyzer	OK
11.	Configure BS to next channel		BS CLI	OK
12.	Reboot BS			OK
13.	Verify that MS loses connection		MS CLI and for signal WiMAX Vector Spectrum Analyzer	OK
14.	Verify that MS begins scanning		MS CLI	OK
Repeat steps 6.-13. for channels 5113.5 and 5147.5 MHz				

### A.6.2.3 Deviation from the planned activities

A different set of frequencies has been used, with respect to what previously hypothesized in [3]. This modification has allowed testing the lowest and highest AeroMACS frequencies in the 5091-5150 MHz band.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

## A.6.3 Verification exercise Results

### A.6.3.1 Summary of Verification exercise Results

ID	Result	Description	When observed	Expected result	Obtained result	VO	Comment
1	ODFMA	Verify that both BS and MS use orthogonal frequency-division multiple access	Step 7	OFMA structure	OFMA structure verified	AeroMACS_VO_Interop_01_A	OK- by means of Spectrum Analyzer
2	Size	Verify that both BS and MS use 5 MHz Channel Bandwidth.	Step 8	5 MHz	5 MHz bandwidth confirmed	AeroMACS_VO_Interop_01_B	OK- by means of Spectrum Analyzer
3	Frame	Verify that both BS and MS use 5 ms Frame Length	Step 9	5 ms	5 ms Frame Length verified	AeroMACS_VO_Interop_01_C	OK- by means of Spectrum Analyzer
4	Duplex	Verify that both BS and MS are able to operate in TDD mode	Step 10	TDD	TDD Mode verified	AeroMACS_VO_Interop_01_D	OK- by means of Spectrum Analyzer
5	Freqs	Verify that the Channel Frequencies usable in the AeroMACS are in 5091- 5150 MHz range	Step 4 Step 11	Expected channel frequency	Verified use of channels 5093.5, 5113.5 and 5147.5 MHz	AeroMACS_VO_Interop_01_E	OK- by means of Spectrum Analyzer
6	Scanning	MS starts with the scanning of the spectrum. It should be checked the correct decoding of the preamble by the MS in order to get synchronized with the BS (no step	Step 2 Step 6 Step 14	Scanning procedure	Checked correct preamble decoding and correct UCD/DCD decoding by MS	AeroMACS_VO_Interop_03_A	OK – by MS CLI

		2). In addition, it should be verified the correct decoding of DCD message for getting all the DL parameters (no step 2).					
7	Initial Ranging	Verify that, after successful DL Synchronization, MS send a CDMA code at a power level below PTX_IR_MAX, measured at the antenna connector. Verify that, in case of no RNG-RSP is received at MS side, MS try to send a new CDMA code at the next appropriate initial ranging transmission opportunity (applying the correct MS power increase) until the BS doesn't send RNG-RSP message or until MS doesn't receive a proper RNG-RSP.  Verify the correct reception of Basic CID and Primary CID.	Step 6	IR procedure	Initial ranging procedure verified	AeroMACS_VO_Interop_03_C	OK – by MS CLI
8	Basic	Verify the correct exchange of Service Basic Capability information	Step 6	Basic Negotiation Capabilities	Correct SBC-REQ/SBC-RSP exchange verified	AeroMACS_VO_Interop_03_D	OK – by MS CLI

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

9	Admission	Verify the Admission Control Procedure	Step6	Admission control procedure	Correct Authentication procedure verified	AeroMACS_VO_Interop_03_E	OK – by MS CLI
10	Registration	Verify that BS and MS successfully conclude the registration procedure	Step6	Completed registration procedure	Correct Registration procedure verified	AeroMACS_VO_Interop_03_F	OK – by MS CLI
11	Available Channels	Verify that MS connects successfully to BS for each configured channel	Step 6			AeroMACS_VO_RFReal_01_A	OK – by MS CLI

### A.6.3.2 Analysis of Verification Exercise Results

Many Objectives (Result IDs from 1 to 5 in previous Chapter) were verified by visual inspection of the Spectrum Analyzer wired to the BS. In Figure 6 it is possible to appreciate how OFDMA Mode, TDD Mode, Frame Length, Channel Bandwidth and Channel Frequency are evidenced (together with other information out of scope for this test, like EVM and Modulation).




Figure 6: Spectrum Analyzer connected to AeroMACS BS

During the test the various phases of Initial Network Entry were executed by BS and MS (Results ID from 6 to 10). In particular, looking at the MS CLI, it was possible to follow the preamble detection and the DCD decoding by the MS side during scanning, the various steps of Initial Ranging, the exchange of Service Basic Capabilities Information, the Authentication/Registration procedure, and the final allocation of Service Flows. Some examples are evidenced in the next images.






Figure 7: Preamble Detection by MS



The screenshot shows a WordPad window titled 'Test\_01.txt'. The text content is as follows:

```
11:10:30:159 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:162 RT : MPI COMP-DLMAP RSSI:-87 CINR:14 FN:656000
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:1 CodeRate:0
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:1 CodeRate:2
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:2 CodeRate:0
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:2 CodeRate:2
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:3 CodeRate:0
11:10:30:162 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:3 CodeRate:1
11:10:30:163 RT : UMAC:SRC->LMAC: DCD: Coding Scheme:0 MOD:3 CodeRate:2
11:10:30:163 RT : MAC->PHY: Sending DCD Config
11:10:30:163 RT : Initail Tx Power :20 Eirxp:-45 BSEirp:40 DLRssi:-87
11:10:30:163 RT : Recvd MPI_PHY_DCD_CFG_CFM indication = 0
11:10:30:167 RT : FN:656002 CDMA Code:3 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:167 RT : LMAC-SRC : IR - CDMA index : 3 SubChnl Off : 0 Sym off : 0
frameNum:0 powerLvl:0 repCode:0 ranging slot:0 rang_type:0
11:10:30:366 RT : RNG: T3 RNG-RSP T3 timer expired FN:656041 RetryCnt:25 Max-
Retries:0
```

Figure 8: DCD Decoding by MS



The screenshot shows a WordPad window titled 'Test\_01.txt'. The text content is as follows:

```
Retries:3
11:10:30:966 RT : LMAC SRC : T2 Tmr For BroadCast Rng Oppur Is Activated
11:10:30:966 RT : OLPC MAC->PHY :PRAM CHNG Time-Off:0 Power-Off:35 Freq-Off:0
11:10:30:966 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:966 RT : FN:656162 CDMA Code:0 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:967 RT : LMAC-SRC : IR - CDMA index : 0 SubChnl Off : 0 Sym off : 0
frameNum:0 powerLvl:0 repCode:0 ranging slot:0 rang_type:0
11:10:30:987 RT : LMAC: RNG RSP Received FN:656166
11:10:30:987 RT : Code:0 Syml:0 Chnl:0 FrnNo:35 AttrPres:1 Basic-CID:0
PrimCID:0
11:10:30:987 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:38 Power-Off:35
11:10:30:987 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:987 RT : RNG RSP : Rng status : 3 ( 1 = Cont; 2 = Abort ; 3 =
Success)
11:10:30:987 RT : UMAC SRC : STATE : IR_CONTENTION : Waiting For CDMA Alloc
IE
11:10:30:001 RT : UMAC SRC : Received IE : CDMA Alloc
```

Figure 9: Initial Ranging - the MS receives a RNG\_RSP with Status Success

```
Test_01.txt - WordPad
File Edit View Insert Format Help
11:10:31:467 RT : Deleting Initial-Ranging connection-CQID: 16 CID:0
11:10:31:467 RT : UMAC SRC : The Basic and Primary CID's Are Updated
11:10:31:467 RT : LMAC: Deleting UL CID: 0 CQID:16
11:10:31:467 RT : DLQConfigReq Cid :12 :: CQID :3
11:10:31:467 RT : MSC : Preparing SBC REQ
11:10:31:467 RT : UL-Flow Config REQ: CID:12 CQID:17
11:10:31:468 RT : DLQConfigReq Cid :1011 :: CQID :4
11:10:31:468 RT : UL-Flow Config REQ: CID:1011 CQID:18
11:10:31:468 RT : Resource Clearance - SF State:0 mDelSf:1 AckCnt:254
11:10:31:468 ERROR : Invalid MSC State:3
11:10:31:516 RT : UL FEC Code Changed from 2 to 0
11:10:31:536 RT : MSC : SBC-REQ sent to BS - T18 SBC RSP Timer is Activated FN:656276
11:10:31:601 RT : SBC-RSP is received from BS
11:10:31:602 RT : SBC RSP : ATH policy From BS:0 MS:0
11:10:31:602 RT : CMAC Validation flag: False MS AuthCode:0 BS AuthCode:0
For Help, press F1 NUM
```

Figure 10: SS Basic Capabilities Exchange between MS and BS

```
11:10:31:602 RT : MSC : STATE : INITIAL N/W ENTRY REGISTRATION
11:10:31:602 RT : MSC : Preparing REG REQ FN:656289
11:10:31:636 RT : MSC: REG-REQ sent to BS. T6 REG RSP Timer is Activated
11:10:31:661 RT : MPI COMP-DLMAP RSSI:-86 CINR:15 FN:656300
11:10:31:666 RT : MSC : T6 REG RSP Timer is Stopped
11:10:31:666 RT : REG-RSP is received from BS
11:10:31:667 RT : REG RSP:SKIP_ADDR_ACQUISITION Not Processing Currently
11:10:31:667 RT : REG RSP: REG_HO_CONN_PROCESSING_TIME:Not Processing Currently
11:10:31:667 RT : REG RSP: REG_HO_TEK_PROCESSING_TIME:Not Processing Currently
11:10:31:667 RT : REG RSP: REG_SN_REPORT_BASE Not Processing Currently
11:10:31:667 RT : MS : STATE : OPERATIONAL MODE
11:10:31:671 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:29
11:10:31:671 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:31:671 RT : CLPC : Recvd Power adj:8
11:10:31:671 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:25
11:10:31:671 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:31:671 RT : CLPC : Recvd Power adj:8
11:10:31:708 RT : DHCP DISCOVER - Len:576
11:10:31:916 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:21
11:10:31:916 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:31:916 RT : CLPC : Recvd Power adj:8
11:10:32:161 RT : MPI COMP-DLMAP RSSI:-86 CINR:14 FN:656400
11:10:32:166 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:17
11:10:32:166 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:32:166 RT : CLPC : Recvd Power adj:8
11:10:32:401 RT : CSF : DSA Request Received
11:10:32:401 RT : -----
11:10:32:401 RT : DSA/DSC REQ/RSP : Direction          : DL Direction
11:10:32:401 RT : DSA/DSC REQ/RSP : Service Flow ID    : 4
11:10:32:401 RT : DSA/DSC REQ/RSP : CID              : 2021
```

Figure 11: Registration procedure and Service Flow Creation

### A.6.3.3 Considerations on Initial Network Entry Time

EUROCAE WG82 is currently discussing about the need to specify, in the MASPS, a maximum allowed Net Entry Time for AeroMACS MSs. Currently the maximum value required in the draft MASPS is 90 seconds.

Measurements done in this Verification Exercise can be used as input for this topic.

Net Entry Time has of course to be minimized, in order to make the AeroMACS MS ready for operations as soon as possible, after landing or switch on.

There are more ways to reach this goal. One possibility is pre-configuring MSs with the list of frequencies operated at destination airports. This solution would surely minimize the Net Entry Time, but would imply the need to use and maintain databases indicating the frequencies in use for any Airport, Another solution is having the MSs to scan the whole band (5000-5150 MHz) at switch-on (auto-learning). This of course lengthen the Net Entry Time, also considering that various phases of Net Entry involve devices potentially located throughout the world (e.g. in most cases AAA/DHCP Servers will not be

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

located in the visited Airport). Figure 12 describes a possible initial Network Entry procedure comprising MS-to-Network EAP authentication process and multiple Domain authentications.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)




Figure 12: Initial Network Entry Time

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

In this Verification Exercise the Network Entry Time (consisting in Physical/MAC Synchronization, Authentication/Registration and Service Flows Creation) was measured being about 9.330 seconds. This time does NOT include time for self-test and other power up functions. Furthermore, all of the devices involved in the process were located in the same room.

It is worth observing that in this exercise the MS had been previously configured to scan a limited list of frequencies. If instead the MS had to scan the whole frequency band 5000-5150 MHz, an extra time should be considered for physical layer scanning. It is estimated that the order of magnitude of the time needed to span the whole band looking for a valid preamble could be tens of milliseconds per channel. Therefore, assuming for instance this time being 30 ms, the extra-time needed to span the whole band would be  $30\text{ms} * 580 = 17.4$  seconds. This would lead to a total Net Entry Time of  $9.33 + 17.4 = 26.73$  seconds.

It is also worth underlining that this result has been obtained in a controlled environment (the Lab). Real environments (Airports) can introduce huge degradation factors (attenuation, multipath fading, shadowing, Doppler effects, etc.) that may increase the packet error rate and the number of retransmissions, with subsequent increase in the Net Entry Time. For this reason, the 90 seconds currently hypothesized in the draft EUROCAE MASPS as maximum net entry time are considered appropriate.

#### A.6.3.4 Unexpected behaviors/Results

None.

#### A.6.4 Conclusions and recommendations

The Verification Exercise allowed checking the basic AeroMACS functions and Initial Network Entry message exchanges. All the related verification Objectives were checked successfully.

### A.7 Verification Exercise # LAB1\_2 Power Control Report

#### A.7.1 Verification Exercise Scope

The purpose of this Verification Exercise is checking that the MS properly applies an Open/Closed Loop Power Control procedure and that the physical measurements which drive them are correct within specified tolerances.

#### A.7.2 Conduct of Verification Exercise

##### A.7.2.1 Verification Exercise Preparation

The same test bed described in A.6.2.1 was used.

##### A.7.2.2 Verification Exercise execution

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

76 of 100

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on MS			OK
2.	Switch on BS			OK
3.	Enable OL (passive) PC and disable CL PC		Mngt PC connected to MS	OK
4.	Verify that MS connects successfully and properly estimates RSSIs		Mngt PC connected to MS	OK
5.	Verify that MS properly operates in open loop PC		Mngt PC connected to MS	OK
6.	Disable OL PC and enable CL PC		Mngt PC connected to MS	OK
7.	Verify that MS properly applies CL PC		Mngt PC connected to MS	OK

### A.7.2.3 Deviation from the planned activities

None

## A.7.3 Verification exercise Results

### A.7.3.1 Summary of Verification exercise Results

ID	Result	Description	When observed	Expected result	Obtained result	VO	Comment
1.	Open Loop	Verify that the MS	Step 5	Power Control	OL passive	AeroMACS_VO_Interop_10_A	OK – by MS CLI

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

77 of 100

	PC	properly applies a (passive) open loop power control technique		Steps	PC steps correctly verified		
2.	Closed Loop PC	Verify that the MS properly applies a closed loop power control technique	Step 7	Power Control Steps	CL PC steps correctly verified	AeroMACS_VO_Interop_10_B	OK – by MS CLI

### A.7.3.2 Analysis of Verification Exercise Results

The Open Loop passive Power Control has been tested first, during the Initial Ranging phase: from the MS CLI it was possible to observe that the MS starts transmitting a CDMA code at the lowest power level in the transmission opportunity allocated by the BS with the previous UL-MAP message (or the optional Compressed DLMAP-ULMAP). Then the MS starts increasing the transmitting power at 1dB steps, until it does not receive a RNG-RSP from the BS.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

```

Test_01.txt - WordPad
File Edit View Insert Format Help
repCode:0 ranging_slot:0 rang_type:0
11:10:30:366 RT : RNG: T3 RNG-RSP T3 timer expired FN:656041 RetryCnt:25 Max-Retries:0
11:10:30:366 RT : LMAC_SRC : T2-Tmr-Ful BroadCast-Rng Oppur_Is Activated
11:10:30:366 RT : <OLPC MAC->PHY :PRAM CHNG Time-Off:0 Power-Off:38 Freq-Off:0
11:10:30:367 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:367 RT : FN:656042 CDMA Code:2 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:367 RT : LMAC-SRC : IR - CDMA index : 2 SubChnl Off : 0 Sym off : 0 frameNum:0 powerLvl:0
repCode:0 ranging_slot:0 rang_type:0
11:10:30:566 RT : RNG: T3 RNG-RSP T3 timer expired FN:656081 RetryCnt:25 Max-Retries:1
11:10:30:566 RT : LMAC_SRC : T2-Tmr-Ful BroadCast-Rng Oppur_Is Activated
11:10:30:566 RT : <OLPC MAC->PHY :PRAM CHNG Time-Off:0 Power-Off:37 Freq-Off:0
11:10:30:566 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:567 RT : FN:656082 CDMA Code:0 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:567 RT : LMAC-SRC : IR - CDMA index : 0 SubChnl Off : 0 Sym off : 0 frameNum:0 powerLvl:0
repCode:0 ranging_slot:0 rang_type:0
11:10:30:661 RT : MPI COMP-DLMAP RSSI:-86 CINR:17 FN:656100
11:10:30:766 RT : RNG: T3 RNG-RSP T3 timer expired FN:656121 RetryCnt:25 Max-Retr
11:10:30:766 RT : LMAC_SRC : T2-Tmr-Ful BroadCast-Rng Oppur_Is Activated
11:10:30:766 RT : <OLPC MAC->PHY :PRAM CHNG Time-Off:0 Power-Off:36 Freq-Off:0
11:10:30:766 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:767 RT : FN:656122 CDMA Code:1 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:767 RT : LMAC-SRC : IR - CDMA index : 1 SubChnl Off : 0 Sym off : 0 frameNum:0 powerLvl:0
repCode:0 ranging_slot:0 rang_type:0
11:10:30:966 RT : RNG: T3 RNG-RSP T3 timer expired FN:656161 RetryCnt:25 Max-Retries:3
11:10:30:966 RT : LMAC_SRC : T2-Tmr-Ful BroadCast-Rng Oppur_Is Activated
11:10:30:966 RT : <OLPC MAC->PHY :PRAM CHNG Time-Off:0 Power-Off:35 Freq-Off:0
11:10:30:966 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:10:30:966 RT : FN:656162 CDMA Code:0 Sub-chnlOff:0 SymbolOff:0 RNG-Type:0
11:10:30:967 RT : LMAC-SRC : IR - CDMA index : 0 SubChnl Off : 0 Sym off : 0 frameNum:0 powerLvl:0
repCode:0 ranging_slot:0 rang_type:0
11:10:30:987 RT : LMAC: RNG RSP Received FN:656166
11:10:30:987 RT : Code:0 SymbL:0 Chnl:0 FrmNo:35 AttrPres:1 Basic-CID:0 PrimCID:0
11:10:30:987 RT : CLPC : LMAC_SRC : PRAM CHNG Time-Off:38 Power-Off:25
    
```

Figure 13: Open Loop passive Power Control Protocol

The Closed Loop Power Control algorithm is activated after the BS and the MS have exchanged the reciprocal Capabilities, after Ranging.

During the test, the Variable attenuator has been gradually increased by a specified amount of dBs, and it has been verified that the MS has subsequently received commands from the BS (PMC-REQ messages) to gradually increase its Transmitted Power by the same amount of dBs.

```

Test_01.txt - WordPad
File Edit View Insert Format Help
11:12:31:671 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:12:31:671 RT : CLPC : Recvd Power adj:8
11:12:31:671 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:25
11:12:31:671 RT : MAC -> PHY : PHY PARAM CHNG REQ
11:12:31:671 RT : CLPC : Recvd Power adj:8
11:12:31:916 RT : CLPC : LMAC-SRC : PRAM CHNG Time-off:0 Power-Off:21
11:12:31:916 RT : MAC -> PHY : PHY PARAM CHNG REQ
    
```

Figure 14: Closed Loop Power Control adjustment at the MS

### A.7.3.3 Unexpected behaviors/Results

None.

### A.7.4 Conclusions and recommendations

It was verified that the equipment properly implements OLPC and CLPC protocols.

## A.8 Verification Exercise # LAB1\_3 Quality of Service Report

### A.8.1 Verification Exercise Scope

The purpose of this Test Case is to verify that all QoS related requirements are satisfied (SF creation and deletion, traffic parameters, bandwidth management) for all the QoS scheduling Types defined.

### A.8.2 Conduct of Verification Exercise

#### A.8.2.1 Verification Exercise Preparation

The test bed described in 15 was used (no need for Spectrum Analyzers in this case).




Figure 15: QoS - Test bed

### A.8.2.2 Verification Exercise execution

Please note that in this Test Case, 1 Service Flow (SF) means 1 SF DL and 1 SF UL.

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on BS			OK
2.	Set 1 SF (SF1) with the scheduling type (QoS class) to be used as 1 among nrtPS/rtPS		Mngt PC connected to ASN-GW/AAA	OK
3.	Switch on MS			OK
4.	Start an IP Flow not compatible with the SF Classification for DL (then for UL) traffic	Using IPERF	IPERF @ PC connected to ASN-GW x DL (MS x UL)	OK
5.	Verify that the IP packets are not transferred on the air interface	Using IPERF	IPERF @ PC connected to MS x DL (ASN-GW x UL)	OK
6.	Change the IP Flow with a configuration compatible with the SF Classification for DL (then for UL) traffic	Using IPERF	IPERF @ PC connected to ASN-GW x DL (MS x UL)	OK
7.	Verify that the IP packets are transferred on the air interface	Using IPERF	IPERF @ PC connected to MS x DL (ASN-GW x UL)	OK
8.	Verify that data exceeding the MSTR is dropped or delayed	Using IPERF	IPERF @ PC connected to MS x DL (ASN-GW x UL)	OK
9.	Verify that all traffic parameters related to the QoS class respect requirements		Mngt PCs connected to MS and BS	OK

10.	Set 1 additional SF (SF2) with the same configuration of the SF of step 2		Mngt PC connected to ASN-GW/AAA	OK
11.	Restart MS			OK
12.	Start two IP Flow one compatible with SF1 configuration and the other with SF2. SF1 throughput > SF2 throughput SF1 throughput + SF2 throughput > Channel capacity	Using IPERF	IPERF @ PC connected to ASN-GW x DL (MS x UL)	OK
13.	Check fairness between flows (SF1 throughput = SF2 throughput)	Using IPERF	IPERF @ PC connected to MS x DL (ASN-GW x UL)	OK
14.	Switch off MS			OK
15.	Pass to another scheduling type (QoS class) and repeat steps from 2 to 14 until all types have been tested			OK

### A.8.2.3 Deviation from the planned activities

None.

## A.8.3 Verification exercise Results

### A.8.3.1 Summary of Verification exercise Results

ID	Result	Description	When observed	Expected result	Obtained result	VO	Comment
1	MSTR	Verify that the Maximum Sustained Traffic Rate value for a SF is respected	Step 8			AeroMACS_VO_Interop_04_B	OK
2	QoS	Verify that the data traffic for a SF is managed following the QoS configuration	Step 9			AeroMACS_VO_Interop_04_C AeroMACS_VO_Interop_04_D	OK
3	DSA	Verify that the correct DSA procedure is implemented	Step 5 Step 7 Step 9			AeroMACS_VO_Interop_05_A	OK
4	Dynamic BW allocation	Verification of correct allocation of the MAC resources	Step 5 Step 7 Step 8 Step 9 Step 13			AeroMACS_VO_Interop_07_A AeroMACS_VO_Interop_07_D	OK

### A.8.3.2 Analysis of Verification Exercise Results

Both the nrtPS and rtPS Classes of Services were tested, as requested in Step #2. Initially, the SF1 was set with nrtPS Class of Service with the following characteristics:

- Priority= 1 (default)
- Max Baud Rate: 1 Mbps (both for UL and DL)

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

83 of 100

- Classification Rules (both in UL and DL):

- DHCP messages exchange enabled (on ports #67 and #68 in this example)
- ICMP messages exchange enabled (e.g. ping messages)
- NTP messages exchanges (enabled on port #123 in this example)
- UDP messages exchanges enabled (on ports #2222 and #2223 in this example)

An IP flow was then started in DL (using IPERF application running on the PC behind the ASN-GW), and sent to a not allowed destination port (#2220), and it was verified that no UDP messages were sent in any GRE tunnel towards the MS (see Figure 16).

A similar operation was then done in the inverse direction (UL), and it was again verified that no message was transmitted by the MS on the air interface.




Figure 16: Wireshark Log on ASN-GW ports: no transmission for IP flow not compatible with the SF Classification for DL



```

[root@localhost ~]# iperf -c 125.125.40.63 -u -i 1 -l 1024 -t 10 -b 2000k -p 2222
-----
Client connecting to 125.125.40.63, UDP port 2222
Sending 1024 byte datagrams
UDP buffer size: 108 KByte (default)
-----
[ 3] local 125.125.4.55 port 43105 connected with 125.125.40.63 port 2222
[ ID] Interval      Transfer      Bandwidth
[ 3] 0.0- 1.0 sec   245 KBytes    2.01 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 1.0- 2.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 2.0- 3.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 3.0- 4.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 4.0- 5.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 5.0- 6.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 6.0- 7.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 7.0- 8.0 sec   245 KBytes    2.01 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 8.0- 9.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 9.0-10.0 sec   244 KBytes    2.00 Mbits/sec
[ ID] Interval      Transfer      Bandwidth
[ 3] 0.0-10.0 sec   2.39 MBytes   2.00 Mbits/sec
[ 3] Sent 2443 datagrams
    
```


Figure 18: IPERF Log at the ASN-GW: 2 Mbps requested to be sent in DL

```

-----
Server listening on UDP port 2222
Receiving 1470 byte datagrams
UDP buffer size: 208 KByte (default)
-----
[ 3] local 125.125.40.63 port 2222 connected with 125.125.4.55 port 43105
[ ID] Interval      Transfer      Bandwidth      Jitter    Lost/Total Datagrams
[ 3] 0.0-10.0 sec   1.18 MBytes   990 Kbits/sec  1.461 ms  1234/ 2443 (51%)
^Croot@aeromacs-HP-Compaq-8200-Elite-SFF-PC:/home/aeromacs# iperf -c 125.125.4.55 -u -i 1
-b 2000k -t 10 -p 2222
-----
    
```


Figure 19: IPERF Log at the MS: 1Mbps Max Baud Rate respected

Then, a second Service Flow (SF2) was set with the same characteristics of SF1. However, SF1 was loaded with an IP Flow with Baud Rate= 2Mbps, while SF2 was loaded with an IP Flow with Baud Rate= 3 Mbps (see Figure 20 and Figure 21).



```
[root@localhost ~]# iperf -c 125.125.40.63 -u -i 1 -l 1024 -t 60 -b 2000k -p 2222
-----
Client connecting to 125.125.40.63, UDP port 2222
Sending 1024 byte datagrams
UDP buffer size:  108 KByte (default)
-----
[  3] local 125.125.4.55 port 44685 connected with 125.125.40.63 port 2222
[ ID] Interval      Transfer    Bandwidth
[  3] 0.0- 1.0 sec   243 KBytes  1.99 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 1.0- 2.0 sec   244 KBytes  2.00 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 2.0- 3.0 sec   244 KBytes  2.00 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 3.0- 4.0 sec   244 KBytes  2.00 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 4.0- 5.0 sec   244 KBytes  2.00 Mbits/sec
```

Figure 20: SF1 loaded with 2 Mbps



```
[root@localhost ~]# iperf -c 125.125.40.63 -u -i 1 -l 1024 -t 60 -b 3000k -p 2224
-----
Client connecting to 125.125.40.63, UDP port 2224
Sending 1024 byte datagrams
UDP buffer size:  108 KByte (default)
-----
[  3] local 125.125.4.55 port 57558 connected with 125.125.40.63 port 2224
[ ID] Interval      Transfer    Bandwidth
[  3] 0.0- 1.0 sec   367 KBytes  3.01 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 1.0- 2.0 sec   366 KBytes  3.00 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
[  3] 2.0- 3.0 sec   366 KBytes  3.00 Mbits/sec
[ ID] Interval      Transfer    Bandwidth
```

Figure 21: SF2 loaded with 3 Mbps

The channel attenuation had been set in order to cause a QPSK  $\frac{3}{4}$  Modulation/Coding, with a consequential Channel Capacity equal to 2,81 Mbps, hence much lower than the total bandwidth needed to support the traffic requested by the 2 IPERF applications (3+2=5Mbps), coherently with the condition requested by step #12.

It was observed that the two IP flows were divided fairly between SF1 and SF2 (see Figure 22 and Figure 23). The little difference evidenced is exclusively due to the different observation periods

between the 2 Service Flows: in fact the 2 IPERF transmissions were started manually, so the 2 observation periods are different.

```
root@aeromacs-HP-Compaq-8200-Elite-SFF-PC:/home/aeromacs# iperf -s -u -p 2222
-----
Server listening on UDP port 2222
Receiving 1470 byte datagrams
UDP buffer size:  208 KByte (default)
-----
[  3] local 125.125.40.63 port 2222 connected with 125.125.4.55 port 44685
[  3] 0.0-61.7 sec  9.61 MBytes  1.38 Mbits/sec  16.932 ms 4804/14648 (33%)
^Croot@aeromacs-HP-Compaq-8200-Elite-SFF-PC:/home/aeromacs# |
```

Figure 22: Baud rate on SF1

```
aeromacs@aeromacs-HP-Compaq-8200-Elite-SFF-PC:~$ iperf -s -u -p 2224
-----
Server listening on UDP port 2224
Receiving 1470 byte datagrams
UDP buffer size:  208 KByte (default)
-----
[  3] local 125.125.40.63 port 2224 connected with 125.125.4.55 port 57558
[  3] 0.0-60.8 sec  10.9 MBytes  1.43 Mbits/sec  29.265 ms 10853/21979 (49%)
^Caeromacs@aeromacs-HP-Compaq-8200-Elite-SFF-PC:~$
```

Figure 23: Baud rate on SF2

### A.8.3.3 Unexpected behaviors/Results

None

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

## A.8.4 Conclusions and recommendations

It was verified that all QoS requirements are satisfied for the QoS scheduling Types defined.

## A.9 Verification Exercise # LAB1\_4 Security Report

### A.9.1 Verification Exercise Scope

The purpose of this Test Case is to verify proper working of Security features.

### A.9.2 Conduct of Verification Exercise

#### A.9.2.1 Verification Exercise Preparation

The test bed described in 15 was used, except for one difference: in fact, the ASN-GW and AAA Server were located in different devices.

#### A.9.2.2 Verification Exercise execution

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on MS			
2.	Switch on BS and ASN-GW/AAA			
3.	Establish a communication and verify that the chosen authentication method is supported: No authentication or EAP based authentication		R6 i/f with Wireshark	With Authentication enabled, insert valid credentials

#### A.9.2.3 Deviation from the planned activities

None.

### A.9.3 Verification exercise Results

#### A.9.3.1 Summary of Verification exercise Results

ID	Result	Description	When	Expected	Obtained	VVO	Comment
----	--------	-------------	------	----------	----------	-----	---------

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

89 of 100

			observed	result	result		
1.	No Authentication	Verify that authentication and key exchange steps are skipped	Step 3	Network entry without authentication		AeroMACS_VO_Interop_11_A	ASN-GW/AAA shall be configured with no Authentication
2.	Authentication	Verify that authentication and key exchange steps are present	Step 3	Network entry with authentication		AeroMACS_VO_Interop_11_B	

### A.9.3.2 Analysis of Verification Exercise Results

The ASN-GW was initially configured in order not to require Authentication to the MS entering the Network; BS and MS were switched on, and the MS started the Net Entry procedure, that was completed successfully. The related messages exchange in the ground network between BS, ASN-GW and DHCP Server is evidenced in the Wireshark log shown in Figure 24.

No.	Time	Source	Destination	Protocol	Info
1	0.000000	125.125.40.32	125.125.40.48	WIMAX	MS_PreAttachment_Req - MSID:00:00:77:b6:90:ac, TID:0x0001
2	0.000735	125.125.40.48	125.125.40.32	WIMAX	MS_PreAttachment_Rsp - MSID:00:00:77:b6:90:ac, TID:0x0001
3	0.002398	125.125.40.32	125.125.40.48	WIMAX	MS_PreAttachment_Ack - MSID:00:00:77:b6:90:ac, TID:0x0001
4	0.047872	125.125.40.32	125.125.40.48	WIMAX	MS_Attachment_Req - MSID:00:00:77:b6:90:ac, TID:0x0002
5	0.048230	125.125.40.48	125.125.40.32	WIMAX	MS_Attachment_Rsp - MSID:00:00:77:b6:90:ac, TID:0x0002
6	0.049540	125.125.40.32	125.125.40.48	WIMAX	MS_Attachment_Ack - MSID:00:00:77:b6:90:ac, TID:0x0002
7	0.052357	125.125.40.48	125.125.40.32	WIMAX	Path_Reg_Req - MSID:00:00:77:b6:90:ac, TID:0x0001
8	0.051634	125.125.40.48	125.125.40.32	WIMAX	Path_Reg_Req - MSID:00:00:77:b6:90:ac, TID:0x0001
9	0.768373	125.125.40.32	125.125.40.48	WIMAX	Path_Reg_Rsp - MSID:00:00:77:b6:90:ac, TID:0x0001
10	0.769138	125.125.40.48	125.125.40.32	WIMAX	Path_Reg_Ack - MSID:00:00:77:b6:90:ac, TID:0x0001
11	6.162729	0.0.0.0	255.255.255.255	DHCP	DHCP Discover - Transaction ID 0x96976e
12	6.164795	125.125.40.48	125.125.40.125	DHCP	DHCP Discover - Transaction ID 0x96976e
13	6.166467	125.125.40.125	125.125.40.48	DHCP	DHCP Offer - Transaction ID 0x96976e
14	6.166666	125.125.40.48	125.125.40.63	DHCP	DHCP offer - Transaction ID 0x96976e
15	6.262676	0.0.0.0	255.255.255.255	DHCP	DHCP Request - Transaction ID 0x96976e
16	6.262928	125.125.40.48	125.125.40.125	DHCP	DHCP Request - Transaction ID 0x96976e
17	6.264122	125.125.40.125	125.125.40.48	DHCP	DHCP ACK - Transaction ID 0x96976e
18	6.267553	125.125.40.48	125.125.40.63	DHCP	DHCP ACK - Transaction ID 0x96976e
19	6.761514	125.125.40.63	125.125.4.55	NTP	NTP client
20	6.761552	125.125.40.63	125.125.4.55	NTP	NTP client
21	6.761552	125.125.40.63	125.125.4.55	NTP	NTP client
22	6.761567	125.125.40.63	125.125.4.55	NTP	NTP client
23	6.761568	125.125.40.63	125.125.4.55	NTP	NTP client
24	6.763114	125.125.4.55	125.125.40.63	NTP	NTP server
25	6.763125	125.125.4.55	125.125.40.63	NTP	NTP server

Frame 18: 350 bytes on wire (2800 bits), 350 bytes captured (2800 bits)  
 Linux cooked capture  
 Internet Protocol, Src: 125.125.40.48 (125.125.40.48), Dst: 125.125.40.63 (125.125.40.63)  
 Generic Routing Encapsulation (IP)  
 Internet Protocol, Src: 125.125.40.48 (125.125.40.48), Dst: 125.125.40.63 (125.125.40.63)

```

0000  00 04 00 01 00 06 68 05  ca 0c 68 00 00 00 08 00  .....h..h....
0010  45 00 01 4e d4 31 00 00  ff 2f 9b 04 7d 7d 28 30  E..N.l..../.}}(0
0020  7d 7d 28 20 20 00 08 00  00 00 00 01 45 00 01 32  }}(. ... ..E..2
0030  d4 31 00 00 ff 11 9b 1f  7d 7d 28 30 7d 7d 28 3f  .l.....}}(0}}(?)
0040  00 43 00 01 1e f9 ac 02 01 06 01 00 96 97 6e  .C.D.....n
0050  00 00 00 00 00 00 00 00  7d 7d 28 2f 00 00 00 00
    
```

Figure 24: Net Entry without authentication - WS Log

Subsequently, the test was repeated after having properly reconfigured ASN-GW/AAA Server in order to require an EAP-based Authentication. The complete procedure was verified.

Figure 25 shows the related Log file, registered at the ASN-GW. In particular, it is possible to appreciate the following steps:

- In step #7 in Figure 25 the ASN-GW sends the ID request to the BS (that has opened a GRE tunnel towards the MS), receiving the BS response (in step #8) containing the MS MAC address and realm.
- The ASN-GW sends an Access-Request to the AAA Server, starting the Authentication Process, and the AAA Server replies with an Access-challenge, after having verified the presence of the MS in its MSs list. This message contains the EAP Message type and the keys to be exchanged in the next transactions.
- The ASN-GW encapsulates the received message in an EAP-REQ to the MS, to which the MS answers with a EAP RSP (Client Hello). The ASN-GW forwards the Client-Hello to the AA Server (step #15 in Figure 25).
- The AAA Server replies the ASN-GW with an Access-challenge (Server-hello) containing also the Server Certificate, and the Request of the Client Certificate. The ASN-GW encapsulates this information in the subsequent EAP-Request to the MS

- The MS answers to the ASN-GW with its Client Certificate, and other information (Client Key Exchange, Certif. Verify, Change Cypher Spec, etc). The ANS-GW encapsulates this information for the AAA Server in step #19
- After a series of acknowledges among the three involved parties, the AAA Server accepts the whole procedure with the Access-accept message in step #24, including the Home Agent Address with which the ASN-GW will create the tunnel for data exchange (PC behind ASN-GW)
- After having successfully created a tunnel with the HA, the ASN-GW sends an EAP\_Transfer (Success) to the MS, and subsequently the Key\_Change\_Directive, containing the keys for Air ciphering (step #35)
- The MS sends back a Key\_Change\_Ack and then the first ciphered message (MS\_Attachment\_Req in step #37)
- After a brief exchange of acknowledges, the ASN-GW sends a Path\_Reg\_Req to the MS, meaning that the Authentication Phase has successfully concluded and the final Registration/SF Creation may be started.




Figure 25: EAP-based Authentication Procedure

### A.9.3.3 Unexpected behaviors/Results

None.

### A.9.4 Conclusions and recommendations

The proper Authentication features were verified in all of the impacted devices (MS, BS, ASN-GW, AAA Server).

## A.10 Verification Exercise # LAB1\_5 Radio Characteristics Requirements Report

### A.10.1 Verification Exercise Scope

The purpose of this Verification Exercise is to verify that the BS Radio characteristics requirements are satisfied.

### A.10.2 Conduct of Verification Exercise

#### A.10.2.1 Verification Exercise Preparation

The same test bed described in A.6.2.1 was used, except for the fact that a MS was not needed in this case.

#### A.10.2.2 Verification Exercise execution

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on MS			Not executed as not needed
2.	Switch on BS			OK
3.	Verify that MS connects successfully		Mngt PCs connected to MS and BS	Not executed as not needed
4.	Send payload to be transmitted by BS		Mngt PCs connected to BS	Not executed as not needed. The BS starts transmitting autonomously at the start-up.
5.	Verify the tune of center frequencies by the BS		WiMAX Spectrum	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

93 of 100

			Analyzer	
6.	Verify the supported 5MHz channelization		WiMAX Spectrum Analyzer	OK

### A.10.2.3 Deviation from the planned activities

Steps 1, 3, 4 were not executed as not needed (the BS starts transmitting autonomously at the start-up).

## A.10.3 Verification exercise Results

### A.10.3.1 Summary of Verification exercise Results

ID	Result	Description	When observed	Expected result	Obtained result	VO	Comment
1.	BS TX Spectrum Mask	Verify the tune of center frequencies by the BS	Step 5	BS Centre Frequency tolerance better than $\pm 2 \times 10^{-6}$	BS Centre Frequency tolerance better than $\pm 2 \times 10^{-8}$	AeroMAC S_VO_RF_06_A	OK- by means of Spectrum Analyzer
2.	BS TX Spectrum Mask	Verify the supported 5Mhz channelization	Step 6	5 MHz Channelization	5 MHz Channelization verified	AeroMAC S_VO_RF_06_B	OK- by means of Spectrum Analyzer

### A.10.3.2 Analysis of Verification Exercise Results

The AeroMACS BS prototype spectrum mask was measured. It is represented in Figure 27.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

94 of 100




Figure 26: AeroMACS BS measured Spectral Mask

The BS center frequency error measured was about  $\pm 100$  Hz at 5.091 MHz, i.e. less than  $2 \times 10^{-8}$ .

Note: The BS prototype spectrum mask was implemented making reference to the target mask reported in Figure 27. At the moment of the prototype specification no MOPS were available, and hence no target masks, neither in draft form.




Figure 27: Selex AeroMACS BS prototype target spectrum mask

The target Spectrum Mask adopted has the following attenuations:

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

param	att.	Freq.
A	0 dBr	2.5 MHz
B	-25 dBr	3.2 MHz
C	-32 dBr	5.0 MHz
D	-50 dBr	7.5 MHz

### A.10.3.3 Unexpected behaviors/Results

None.

## A.10.4 Conclusions and recommendations

The AeroMACS BS prototype spectrum mask was measured.

## A.11 Verification Exercise # LAB1\_6 Transmit Power Report

### A.11.1 Verification Exercise Scope

The purpose of this Verification Exercise is to verify that the Transmit Power requirements listed in the Verification Exercise execution Section are satisfied.

### A.11.2 Conduct of Verification Exercise

#### A.11.2.1 Verification Exercise Preparation

The exercise was executed with the test bed described in Figure 2.

#### A.11.2.2 Verification Exercise execution

Step nr.	Action	Action description	PCO (Point of Control and Observation)	Comment
1.	Switch on MS			OK
2.	Switch on BS			OK
3.	Send payload to be transmitted by BS		Mngt PCs connected to BS	OK
4.	Verify the BS output power range		Mngt PC connected to BS and for signal  WiMAX	OK

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

96 of 100

			Spectrum Analyzer	
5.	Verify that if the BS belongs to Class 1, then its transmitted power keeps in the range of $20 < P_{Tx,max} < 23$ dBm for QPSK modulation		Mngt PC connected to BS and for signal  WiMAX Spectrum Analyzer	OK
6.	Lower and raise the Variable attenuator Level at steps of 1 dB		Variable Attenuator	OK
7.	Verify that the MS output power is increased or decreased in order to compensate the power fluctuations	Check the MS TX power with the Spectrum Analyzer, check the UL MAP IE on the RF Link	Mngt PCs connected to MS and BS, and for signal  WiMAX Spectrum Analyzer	OK

### A.11.2.3 Deviation from the planned activities

None.

## A.11.3 Verification exercise Results

### A.11.3.1 Summary of Verification exercise Results

ID	Result	Description	When observed	Expected result	Obtained result	VO	Comment
1.	Verify the BS output power range		Step 4			AeroMACS_VO_RF_08_D	OK- by means of Spectrum Analyzer
2.	Verify that if the BS belongs to Class 1, then its transmitted power		Step 5			AeroMACS_VO_RF_07_A	OK- by means of Spectrum Analyzer

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
www.sesarju.eu

97 of 100

	keeps in the range of $20 < P_{Tx,m} < 23$ dBm for QPSK modulation						
3.	Transmit Power Control and Relative Step accuracy	Verify power control procedure during initial ranging phase, Closed Loop and Open Loop Power Control mode	Step 7	Verify that the MS output power is increased or decreased in order to compensate the power fluctuations		AeroMACS_VO_RF_08_A/C	OK- by means of Spectrum Analyzer

### A.11.3.2 Analysis of Verification Exercise Results

The exercise was executed with the test bed described in Figure 2.

In order to verify the BS TX Output power, the total attenuation introduced by the attenuator and cables between the BS under test and the Spectrum Analyzer was measured. It resulted being 16 dB.

Then the Spectrum Analyzer measured the BS "Band Power", that is the BS TX power actually contained in the 5 MHz band, evidenced by markers in Figure 28.

The resulting BS TX Output Power was calculated as  $(16 + 6.87) = 22.87$  dBm (Class 1).




Figure 28: BS Output Band Power

The OL passive Power Control and CL Power Control procedures have been verified. Analysis is shown in A.7.3.2.

### A.11.3.3 Unexpected behaviors/Results

None.

### A.11.4 Conclusions and recommendations

The BS TX Output Power has been measured. The OL passive Power Control and CL Power Control procedures have been successfully verified.

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
 www.sesarju.eu

**-END OF DOCUMENT-**

founding members



Avenue de Cortenbergh 100 | B -1000 Bruxelles  
[www.sesarju.eu](http://www.sesarju.eu)